



Foreword

Welcome to the SP Energy Networks' Innovation Funding Incentive (IFI) Annual Report for 2008/09.

It has been another significant year for the energy sector with increased focus on the challenges of carbon emission reduction and the vital role of innovation in delivering 2020 and 2050 targets. Research, Development and Demonstration (RD&D) will not only contribute to setting the strategic directions for the industry but also help to shape the way we



produce, transport and consume energy. The government's 2020 vision for the transmission system and desire to deliver smart meters in every home are but two initiatives aimed at transferring Britain into a low carbon economy that is sustainable, affordable and places the UK at the forefront of technological developments. Utility companies will have a central role to play in developing and delivering this economy and the IFI programme contributes considerably towards this.

Over the past five years many notable technical solutions have been developed under the IFI programme contributing to all aspects of managing the electricity network. Some of our IFI projects such as the overhead line fault passage indicators have now been put into practice and visible benefits are being realised in terms of quicker fault location and customer restoration, whilst others have been converted into design recommendation such as the distance of wind turbines from overhead transmission lines. This year the 4energy low carbon comms cooling project has shown a potential for reducing energy consumption in communication cabinets by at least 80%. As part of our ongoing IFI strategy we will continue to consolidate on our portfolio of projects and utilise our allowances sensibly and effectively to ensure technological advances are realised to meet future industry challenges.

We continue to work and collaborate with our parent company Iberdrola on RD&D projects ensuring benefits are shared within the group and the industry. Experiences on projects in areas of electric vehicles and smart meters among others are shared to enhance the understanding and impact of these technologies. The nature of many new technologies is such that not only closer collaboration between DNOs is required but also with other stakeholders in the energy value chain including suppliers, generators and consumers. We think RD&D will play an increasingly important role in the coming years and will contribute significantly to the delivery of the UK vision and targets.

Alan Bryce Director

SP Energy Networks

Clan a Byrn



Contents

FOR	EWORD	1
1	INTRODUCTION & BACKGROUND	4
1.1	Context	4
1.2	Innovation Funding Incentive (IFI)	4
1.3	Registered Power Zone (RPZ)	4
2	SP ENERGY NETWORKS STRUCTURE	5
3	OVERVIEW	6
3.1	IFI	6
3.2	RPZ	7
	Pipeline RPZ application	
4	SUMMARY TABLES	8
5	ACHIEVEMENTS FOR 2008/09	9
5.1	Development of Partnerships	9
5.2	Deployment of Trials	^
5.2	Deployment of Trials	9
5.3	Identifying the Issues and Developing the Enablers	
		.10
5.3	Identifying the Issues and Developing the Enablers	.10 .11
5.3 6	Identifying the Issues and Developing the Enablers	.10 .11 .11
5.3 6 6.1	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling	.10 .11 .11
5.3 6	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS. Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials	.10 .11 .11 .11
5.3 6 6.1	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling	.10 .11 .11 .11 .12
5.3 6 6.1 6.2	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS. Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials IFI 0409 – LV Fault Location Device IFI 0709 - Network Monitoring using Web Systems	.10 .11 .11 .11 .12 .12
5.3 6 6.1	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS	.10 .11 .11 .11 .12 .12
5.366.16.2	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS. Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials IFI 0409 – LV Fault Location Device IFI 0709 - Network Monitoring using Web Systems	.10 .11 .11 .12 .12 .12
5.3 6 6.1 6.2 7 APP	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS	.10 .11 .11 .12 .12 .13 .14
5.3 6 6.1 6.2 7 APP	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials IFI 0409 – LV Fault Location Device IFI 0709 - Network Monitoring using Web Systems LOOKING AHEAD - FOCUS FOR 09/10 ENDIX A – IFI HIGHLIGHTS FOR 08/09 SUBMITTED TO ENA R&D BROCHURE ENDIX B – EXPENDITURE BREAKDOWN OF PROJECTS BETWEEN LICENCES Summary Table Notes	.10 .11 .11 .12 .12 .13 .14 .17
5.3 6 6.1 6.2 7 APP	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials IFI 0409 – LV Fault Location Device IFI 0709 - Network Monitoring using Web Systems LOOKING AHEAD - FOCUS FOR 09/10 ENDIX A – IFI HIGHLIGHTS FOR 08/09 SUBMITTED TO ENA R&D BROCHURE ENDIX B – EXPENDITURE BREAKDOWN OF PROJECTS BETWEEN LICENCES Summary Table Notes Cost Breakdown	.10 .11 .11 .12 .12 .13 .14 .17 .18
5.3 6 6.1 6.2 7 APP	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS	.10 .11 .11 .12 .12 .13 .14 .18 .18
5.3 6 6.1 6.2 7 APP	Identifying the Issues and Developing the Enablers REALISED BENEFITS FROM IFI PROJECTS Benefits from Adopted IFI Projects IFI 0704 - 4E Comms Cooling Benefits from IFI Trials IFI 0409 – LV Fault Location Device IFI 0709 - Network Monitoring using Web Systems LOOKING AHEAD - FOCUS FOR 09/10 ENDIX A – IFI HIGHLIGHTS FOR 08/09 SUBMITTED TO ENA R&D BROCHURE ENDIX B – EXPENDITURE BREAKDOWN OF PROJECTS BETWEEN LICENCES Summary Table Notes Cost Breakdown	.10 .11 .11 .12 .12 .13 .14 .18 .18 .18



APPENDIX C – METHODOLOGY FOR NPV CALCULATIONS IN IFI PROJECTS	22
APPENDIX D – PROJECT REPORTS IFI PROJECTS	27
APRIL 08 – MARCH 09	27
IFI 0402 - Single Phase LV Voltage Regulators	28
IFI 0404 - Alternative Insulating Oils – Phase 1	29
IFI 0406 - Overhead Line Fault Passage Indicators	
IFI 0409 - LV Fault Location Devices	31
IFI 0502 - Fault Level Monitor Project	32
IFI 0505 - Supergen V - AMPerES	33
IFI 0507 - Sensor Networks (Smart Dust) – Phase 2	35
IFI 0508 - Development of Redox flow battery for energy storage	36
IFI 0509 - Superconducting Fault Current Limiter	37
IFI 0510 - Innovative Protection Solutions	38
IFI 0511 - Voltage Control ACTIV (EATL)	39
IFI 0513 - Thermal modelling and Active Network Management	
IFI 0515 - Power System Demonstration Centre (PNDC)	42
IFI 0526 - PD Monitoring of Cables (11 & 33kV)	
IFI 0532 - AURA-NMS	
IFI 0535 - Radiometric Arc Fault Location	46
IFI 0540 - MANtIS (Managing Active Networks through Intelligent Systems)	47
IFI 0607 - LV Network Automation	
IFI 0615 - ScottishPower Advanced Research Centre (SPARC)	49
IFI 0618 - Supergen 1 – FlexNet	
IFI 0619 - Advanced Cable Technologies	53
IFI 0620 - Tower Foundation Radar	
IFI 0621 – Energy Innovation Centre	55
IFI 0624 - Impact of Climate Change, Energy (Phase 2) - MET Office	
IFI 0625 - Vegetation Management - ADAS	
IFI 0628 - Asset Decision Support Dashboard	
IFI 0701 - ENA IFI Projects	
IFI 0702 - Lattice Steel Tower Protective Coatings	
IFI 0704 - 4energy Low Carbon Comms Cooling	
IFI 0706 - Ashton Hayes Microgrid	
IFI 0707 - Wind Turbine Effects on Transmission Lines	
IFI 0708 - Health Indices for Asset Management Decision Making	
IFI 0709 - Sub.net Monitoring	
IFI 0710 - GB SQSS Review Studies	
IFI 0711 - 3 rd Party ROEP Risk Assessment	
IFI 0712 - BT 21 st Century Protection Solutions (BT21CN)	
IFI 0801 - IEC 61850 Application in SP - Transmission	
Strategic Technology Programme: Overhead Network Module 2	
Strategic Technology Programme: Cables Module 3	
Strategic Technology Programme: Substations Module 4	
Strategic Technology Programme: Distributed Energy Resources Module 5	



1 Introduction & Background

1.1 Context

As part of the most recent Distribution and Transmission Price Control Reviews (DPCR/TPCR), Ofgem introduced the Innovation Funding Incentive (IFI) as a mechanism to promote and encourage network related Research & Development (R&D). In addition to the development focus of the IFI, a second incentive the Registered Power Zone (RPZ) was introduced for Distribution Licensees to promote the use of novel techniques in the connection of Distributed Generation to the network.

The primary aim of the two incentives is to encourage the electricity network operators to apply innovation in the way they pursue the technical development of their networks. Ofgem recognised that innovation has a different risk/reward balance compared with a network operators' core business. The incentives provided by the IFI and RPZ mechanisms are designed to create a risk/reward balance that is consistent with research, development and innovation. The two main business drivers for providing these incentives at this time are the growing need to efficiently manage the renewal of network assets and to provide connections for an increasing capacity of renewable generation at all voltage levels. These are significant challenges that will both benefit from innovation.

1.2 Innovation Funding Incentive (IFI)

The IFI is intended to provide funding for projects focused on the technical development of distribution and transmission networks, to deliver value (i.e. financial, supply quality, environmental, safety) to end consumers. IFI projects can embrace any aspect of the distribution / transmission system asset management from design through to construction, commissioning, operation, maintenance and decommissioning. The detail of the DNO IFI mechanism is set out in the Special Licence Condition C3, Standard Licence Condition 51 (for the Distribution Licences), the Electricity Transmission Licensees' IFI mechanism is set out in the special licence condition J5 Part 3 or special licence condition D5 part 2, and standard licence condition B16 Part C.

With the extension of IFI to the transmission licences, agreement at the ENA R&D Working Group was given to the creation of a common Good Practice Guide (GPG) considering IFI for electricity distribution, transmission and gas transmission networks; Version 2 of Engineering Recommendation G85 issued in December 07.

1.3 Registered Power Zone (RPZ)

In contrast to the IFI, RPZs are focused specifically on the connection of generation to distribution systems. The estimates made by DNOs as part of the DPCR process indicated that some 10GW of generation could be connected from 2005-10. This generation could connect at every distribution voltage level bringing new system design and operating challenges. RPZs are therefore intended to encourage DNOs to develop and demonstrate new, more cost effective ways of connecting and operating generation that will deliver specific benefits to new distributed generators and broader benefits to consumers generally. The detail of the RPZ mechanism is set out in the Special Licence Condition D2 and the DG Regulatory Instructions and Guidance (RIGs).



2 SP Energy Networks Structure

SP Energy Networks (SPEN) is the part of ScottishPower UK Ltd, which owns and operates the electricity transmission and distribution network of southern Scotland and the electricity distribution network of Merseyside and North Wales. Day-to-day operation of our network, approaching 112,000 km, is conducted by SP Energy Networks, a wholly owned subsidiary of ScottishPower Ltd. Since April 2007 ScottishPower has been part of the Iberdrola Group.

Our transmission and distribution licence assets come under three wholly owned subsidiaries:

- SP Distribution: The electricity network of 33kV and below in southern Scotland
- SP Manweb: The electricity network of 132kV and below in Merseyside and North Wales
- SP Transmission: The electricity network of 132kV and above in southern Scotland

IFI activity is co-ordinated centrally on behalf of these licences, this report relates to R&D activity undertaken on:

- SP Distribution Ltd, referred to as SP-D in this report
- SP Manweb plc, referred to as SP-M in this report
- SP Transmission Ltd, referred to as SP-T in this report




Figure 1: UK Map showing the territory of (a) SP Distribution & SP Transmission and (b) SP Manweb



3 Overview

3.1 IFI


A total of 38 IFI projects are being reported by SP Energy Networks on behalf of the three ScottishPower Network licence areas for the period 1^{st} April 08 – 31^{st} March 09.

At time of writing SPEN has a total of £6.5m authorised IFI projects, representing a levered portfolio of over £33m. The projects cover a breadth of R&D providers from academia, to consultants, to manufacturers with projects ranging in investment from £15k to £1m IFI input, and development timescales of between 6 months and 4 years.

Our R&D activity has increased significantly since the introduction of the IFI. We have continued to focus on leveraging our programme through collaboration with funding bodies, other network operators or external suppliers / manufacturers. In 2008/09 every £1 of SP IFI money invested in a project was levered by c.£4 from other sources:

R&D growth in SPEN (SP-D, SP-M and SP-T) since the introduction of the IFI										
	Expenditure	No. Of	Yearly							
SP-D, SP-M and SP-T	(Internal +	Reported	Programme							
	External)	Projects	Leverage							
2004/05 (Early Start)	£223k	12	c. £1.5m							
2005/06	£546k	36	c. £3m							
2006/07	£1,282k	41	c. £5m							
2007/08	£1,793k	50	c. £7m							
2008/09	£1,978k	38	c. £9m							

Figure 2 R&D expenditure growth SPEN (SP-D, SP-M and SP-T) since the introduction of the IFI





3.2 RPZ


Pipeline RPZ application

As an outcome of the AuRA-NMS and Dynamic Thermal Ratings projects, it is proposed to apply for an RPZ application in 2009/2010 to manage generation constrains in North Wales.

The application will refer to the connection of a number of wind generators to the SP Manweb network in the St Asaph area of North Wales. This area is predominantly rural, and is a rich wind resource. There is presently a number on-shore and offshore wind farms in the area, and further wind farms are either under construction, or at the planning stage.



Plans are being developed which could include an offshore windfarm as well as generation to the south of St Asaph, known as Area 'A', which has been designated for additional wind generation as part of a Welsh Assembly Government' TAN 8 (Technical Adviser Note) initiative.



SP Manweb expects to receive generation connection applications totalling up to 200MW in Area 'A'. A system of constraints will be used to connect the off shore generation, while preventing the ratings of the existing 132kV circuits from St Asaph substation being exceeded. To facilitate the connection of the Area 'A' generation without significant reinforcement of the 132kV network, the constraints scheme will be extended to manage both sites.



4 Summary Tables

The following tables have been adapted from the Regulatory Instructions and Guidance documents (RIGs).

IFI Summary - SP Distribution Ltd Licence Area 08/09	
SP Distribution Ltd Network Revenue	£ 315,210,000
IFI Allowance	£ 1,576,050
Unused IFI Carry Forward to 2008/09	£ 728,150
Number of Active IFI Projects	31
Summary of benefits anticipated from IFI projects 2008/09	£ 160,800 ¹
External expenditure [2008/09] on IFI projects	£ 824,023
Internal expenditure [2008/09] on IFI projects	£ 198,367
Total expenditure [2008/09] on IFI projects	£ 1,022,390
Benefits actually achieved from IFI projects to date	£2,137,000

IFI Summary - SP Manweb plc Licence Area 08/09								
SP Manweb plc Distribution Network Revenue	£ 186,420,000							
IFI Allowance	£ 932,100							
Unused IFI Carry Forward to 2008/09	£ 213,950							
Number of Active IFI Projects	36							
Summary of benefits anticipated from IFI projects 2008/09	£ 107,200 ¹							
External expenditure [2008/09] on IFI projects	£ 634,421							
Internal expenditure [2008/09] on IFI projects	£ 152,364							
Total expenditure [2008/09] on IFI projects	£ 786,835							
Benefits actually achieved from IFI projects to date	£2,137,000							

IFI Summary - SP Transmission Ltd Licence Area 08/09								
SP Transmission Ltd Distribution Network Revenue	£ 179,940,000							
IFI Allowance	£ 899,700							
Unused IFI Carry Forward to 2008/09	£ 412,000							
Number of Active IFI Projects	9							
Summary of benefits anticipated from IFI projects 2008/09	£69,000 ²							
External expenditure [2008/09] on IFI projects	£ 118,118							
Internal expenditure [2008/09] on IFI projects	£ 50,870							
Total expenditure [2008/09] on IFI projects	£ 168,870							
Benefits actually achieved from IFI projects to date	£69,000							

Further detail on these tables is provided in Appendix B of this report.

¹ Added benefits detailed section 7.2

² Added benefits detailed section 7.1



5 Achievements for 2008/09

At the end of 2008/09 the highlights from the SPEN IFI portfolio included:

- Every IFI project undertaken by SP is taken before a panel of senior experts from across the business. Through this process we have:
 - o 38 live projects
 - o 47 projects fully authorised with 2 receiving preliminary approval
 - 5 new projects were authorised during the 2008/09
 - Of the 47 projects, 6 are now complete and either awaiting adoption or formal closure
- Over £9m of leverage obtained
- 20 projects achieving Technology Readiness Level (TRL) 7 (network integration) or above with further trials scheduled
- 3 projects formally adopted into the business with several more near the final stages of trials
- As part of the Iberdrola group, SPEN are actively participating in regular R&D meetings with other network businesses within the group, to recognise synergies and other areas of learning. More information can be obtained at the following link to Iberdrola's Innovation Report 2007-08:



http://www.iberdrola.es/webibd/gc/prod/en/doc/innovacion informe.pdf

5.1 Development of Partnerships

The current programme consists of the following collaborative projects:

- Engineering & Physical Science Research Council (EPSRC) strategic partnership: AuRA-NMS
- EPSRC 3x industry roles in Supergen programmes: Supergen 1 Flexnet; Supergen 3 -Highly Distributed Power Systems; Supergen 5 - AMPerES
- Technology Strategy Board (TSB) technology programme projects: Fault calculations -K/EL/00352; Thermal State Estimation - TP/4/EET/6/I/22088; Redox Flow Cell Battery -TP/3/ERG/6/1/16587(D05/726039); MANtIS - K/EL/00365/00/00
- DNO specific 20 collaborative projects with some / all UK DNOs via EA Technology, ENA
 or through direct collaboration (see Appendix D for details).
- Direct university partnership 1x ScottishPower Advanced Research Centre (SPARC) with the University of Strathclyde.
- Capenhurst Energy Innovation Centre A non-profit trust that over sees the management of the centre in collaboration with ScottishPower, Electricity North West, CE Electric, Scottish & Southern Energy and the North West Development Agency.
- Working with a Glasgow based consortium on the Ultra Low Carbon Vehicle Demonstration Program (ULCVD). This programme was set up by the Technology Strategy Board and will run trials in various locations in the UK. The Glasgow trial will roll out around 40 Electric Vehicles including a charging infrastructure to assess consumer behaviour and practicality of running EV. Although this is not an IFI programme it is expected this trial will initiate further R&D projects to look at the impact of EV.

5.2 Deployment of Trials

Trials are a significant and necessary part of our R&D programme. A trial can consist of:



- Physical network trial a piece of equipment physically installed on the network, following successful development and type testing. The purpose of this trial is to ensure the device integrates with the existing network.
- Software trial the processing of SP network data through an appropriate software model. The purpose of this trial is to prove the quality of a piece of software, and the suitability of SP data formats.

As a trial signifies the latter stages of an R&D lifecycle (Technology Readiness Level 7: *Technology system prototype demonstration in an operational environment*) many of the technologies undertaken since the start of the IFI reflect our work with manufacturers / consultants, which are further down the R&D lifecycle. Further details are provided on specific projects in Appendix D.

5.3 Identifying the Issues and Developing the Enablers

This project initially proposed and led by SPEN, was to develop the first of its kind, in the UK, a full scale 11kV and LV prototyping network as a test-bed for active network management techniques and other 'high risk' technologies.

Whilst not a technological development in itself, this project is a fundamental enabler of technology, with significant potential to accelerate adoption of significant / radical developments across a range of IFI projects. The centre can be used to investigate the impact of intermittent generation and penetration of EV technologies on the LV network as well as testing of new tools and training.

Since late 2008, SPEN have been working with collaborative partners (University of Strathclyde, Scottish & Southern Energy and Scottish Enterprise) to develop the design.

It is aimed to start building the centre in Q2 of 2010 and to be ready by Q2 2011.




Figure 3 Pictorial representation of the Demonstration Facility



6 Realised Benefits from IFI Projects

Whilst not all benefits have a direct monitory value, we have indicated the benefits brought to SPEN in improvements to customer service, reductions to capital cost of equipment and the reduction in energy usage/carbon emissions.

6.1 Benefits from Adopted IFI Projects

IFI 0704 - 4E Comms Cooling

Following the successful installation and testing, the design and development brief under the IFI project has been fully met. 4Energy have been able to develop a flexible package of parts that can be tailored to fit any telecoms site and will ensure that Cisco equipment is maintained in a safe working temperature with an ultra reliable, maintenance free cooling system without the use of energy and maintenance hungry systems. The temperature data gathered during the trial period has proven that traditional air conditioning is not needed in these locations and that 4energy's system offers a genuine alternative.

Without the RFI Cool system the use of air conditioning in summer is unavoidable in telecoms rooms in order to keep Cisco cabinets below 40°C. However, the 8-10°C reduction from 'RFI cool' means that the room temperature can be safely elevated up to 35°C without any harmful effects on the equipment. This opens up the opportunity to use the Directed Air solution developed under this IFI project which guarantees temperatures will remain under 40°C in the Cisco cabinets under Glasgow climatic conditions.

Following the installation of the Directed Air systems with 'no maintenance' filtration the telecom rooms have been held at ambient around 7-10°C hotter than outside environmental temperature which ensures that the Cisco cabinets will be maintained at less than 40°C.

The proposal is to install energy efficiency cooling in telecommunication rooms in major grid sites in which Cisco servers are being located. This initiative will deliver a saving of approximately 40% on the capital cost of installing traditional vapour compression air conditioning.

Once installed a greater than 90% saving versus estimated air conditioning power will be made in those telecommunication rooms.

Comparison Table of Air Conditioning vs. 4energy Solution									
	Aircon cost	4energy Cost	Saving						
Per Site		~40% less than AC							
Power Usage (pa)	~15,000kWh	~1,000kWh	~93%						
Carbon Emissions (pa)	~6,450kgCO ₂	~430kg CO ₂	~6,020 CO ₂						
All Installations (17)		~40% less than AC							
Power Usage (pa)	~255,000kWh	~17,000kWh	~93%						
Carbon Emissions (pa)	~109,650kg CO ₂	~7,310kg CO ₂	~102,340kg CO ₂						



6.2 Benefits from IFI Trials

The following examples are given to demonstrate some of the benefits being delivered from SP's IFI trials:

IFI 0409 - LV Fault Location Device

Since SP EnergyNetworks started using the TP22, it has made a big difference to the customer and to the number of complaints received within the Customer Contacts Team.

If a customer contacts SP EnergyNetworks about multiple interruptions the contact is dealt with within the Contacts Team, who then talk with the TP22 controller who organises the TP to be installed. With this equipment the Contacts Team can give the customer the assurance that the fault is being worked on. Prior to the team having this equipment, they could only advise the customer that the fault would be found in due course but it could take weeks which would result in further interruptions. This meant CML (Customer Minutes Lost) & CI (Customer Interruptions) increased therefore increasing the cost to the business in CML/CI penalties.

As well as the benefit to customers, there have been benefits in both reducing the amount of trial excavations that occur during the use of older techniques of fault location.

Savings For LV Fault Locations		
5% usage on non repair faults	North(117) + South(62)	169 locations
60% success rate	(169 locations) * 0.6	107 successes
Savings	107 * £2500	£268k savings

IFI 0709 - Network Monitoring using Web Systems

Sub.net is a substation based multifunction disturbance recorder, which monitors various aspects of the power network. It is connected to protection VTs and CTs and auxiliary contacts from protection relays and switchgear. Sub.net process the information at site and sends formatted reports of events detected on the network directly to individual users by email.

It is possible to capture an event and distribute the processed data in around three minutes to the parties that can take the appropriate action. Monitors should be able to aid early indication of 11kV fault location, confirm that overhead line protection or automation schemes are functioning properly and determine if circuit breaker operating times are within acceptable limits, in addition to covering the full range of Power Quality phenomenon.

Through the event capture process it is estimated that 3 potentially 'sticky' breakers have been found prior to them having to operate for an actual fault. SPEN estimate that this could have saved as much as £500k. Along with slow/stuck breakers it has been possible to identify the location of transient faults using impedance maps, this part of the project will be developed in 2009/10.



7 Looking Ahead - Focus for 09/10

Our focus for 2009/10 will continue to build on the foundations laid in the five years of IFI and on engagement; trials; adoption and extension.

- Continue to maximise value of programme through collaboration and project leverage.
- Real focus on driving projects through trial and making a decision on implementation.

Improving engagement and activity: With over 38 live projects, SP is strengthening outreach into the business, in addition, during 2008/09 we aim to raise the profile further through internal workshops and linkage to R&D activity in Iberdrola SA.

Increasing the number of network trials: SP recognise the complications and extensive timescales involved in getting multi-party R&D projects off the ground (both technically and contractually), but with a healthy portfolio of approved projects and signed contracts, we can now focus firmly on delivery. SP aim to accelerate projects towards trial with a focus on delivery and adoption. Trials scheduled for 2009/10 include:

- Moving on from data gathering to implementation of algorithm for the Dynamic Ratings / Thermal State Estimation (IFI 0513) project to open loop operation of new protection equipment
- Continuing work with Smarter Grid Solutions in the RPZ application. As the TAN 8/Area
 A RPZ is time sensitive, its is thought that having two options available to increase the
 connection of wind generation
- IFI 0509 Superconducting Fault Current Limiter The project is starting its first network trial with ENW at Bamberbridge s/s. SPEN will begin installation in December 2009 with final commissioning and the SCFCL going 'Live' in February 2010.

Convert successful projects into adoption: Whilst trials on a live network are an essential step in technological development, true value will only occur when technologies are fully embraced and adopted in the business. With several projects successfully completing trials, we aim to focus on formally closing down projects and transferring into the business as an approved product or service.

In order to accelerate the route to adoption, we will continue to work with partners on our proposal for a UK networks demonstrator.



Appendix A – IFI Highlights for 08/09 submitted to ENA R&D Brochure



Fault Current Limiter based on Superconducting Materials

A Consortium comprising CE Electric UK, Electricity North West, Scottish Power Energy Networks, and Applied Superconductor have been working on a superconducting fault current limiter based on bulk BSSCO superconductor for installation in each of the DNOs' respective 11kV networks.




Figure 1 Consortium Network Areas

Fault levels have always been a constraint in the development of electricity networks and have been controlled by increasing source impedance, (either by installing higher impedance components or by splitting networks) or by purchasing components designed for higher fault levels. With the continued increase in electrical load, the redevelopment of city centre areas and the increase in embedded generation, particularly CHP in city centres, but also renewable energy generators such as wind, the pressure to cope with rising fault levels continues and is likely to increase.

Superconductors, when in their superconducting state are perfect conductors and have zero resistance to the flow of electrical current. They lose their superconducting properties when they are subjected to current, magnetic

fields or temperature above critical values, and 'quench' back to their normal (poor) conducting state. This is a physical property of the material so a fault current limiter using superconducting material does not require external triggering and is exempt from fault detection failures. It fails to a safe (resistive) state.




Figure 2 Trace of FCL 'Quenching'

By harnessing this physical property an effective fault current limiter can be designed which is low loss during normal operation, yet quenches to limit fault current. The quench transition happens quickly (~1ms) and early during the onset of a fault, prior to the first peak, allowing lower rated switchgear and components to be deployed.



Figure 3 Trial 1 SCFCL (ENW)



4energy Comms Cooling

An IFI funded investigation and system development project was carried out to innovatively regulate the temperature of CISCO radio equipment inside RFI cabinets within substation telecoms rooms.

This equipment is a key part of Scottish Power's transmission communication network. The subject of the innovation was to develop a cooling solution that doesn't rely on energy and maintenance hungry traditional air conditioning.




Figure 1 Atmospheric and Ambient Temperatures

The objective of 4energy's work was twofold:

- Assess potential cooling solutions for the RFI cabinets
- Develop and install on-line 3 low energy alternative cooling solution to vapour compression air conditioning on heat affected sites

Cooling solutions for RFI cabinets

Following the first site visit SPEN supplied an RFI cabinet in which 4energy installed a simulated heat source and then investigated various heat dissipation techniques to cool the cabinet. Successful off-line testing was completed with encouraging results.

An on-line test was successfully started in December 2007 at Strathaven, with 4 other sites selected to demonstrate installation procedures.

The result of this innovation is that Cisco cabinets have been reduced in temperature by 8-10°C. In total 19 'RFI cool' systems have been delivered for installation.

Without the RFI Cool system the use of air conditioning in summer is unavoidable in telecoms rooms in order to keep Cisco cabinets below 40°C. However, the 8-10°C reduction from 'RFI cool' means that the room temperature can be safely elevated up to 35°C without any harmful effects on the equipment.




Figure 2 Temperature Drop on Installation

This opens up the opportunity to use the Directed Air solution developed under this IFI project which guarantees temperatures will remain under 40°C in the Cisco cabinets under Glasgow climatic conditions.




Figure 3 Complete System at Strathaven

Following the installation of the Directed Air systems with 'no maintenance' filtration the telecom rooms have been held at ambient around 7-10°C hotter than outside environmental temperature which ensures that the Cisco cabinets will be maintained at less than 40°C.



Appendix B – Expenditure Breakdown of Projects between Licences



Summary Table Notes

During the collation of the 05/06 report we revised our methodology for NPV assessments for IFI projects. It is noted that the figures described in the tables should be interpreted with caution, as the figures quoted in the NPVs will only be realised upon completion of the project, and once fully adopted into the business – further information is detailed in Appendix C.

Cost Breakdown

As SP Energy Networks operate distribution and transmission licenses for the SP-D, SP-M and SP-T areas, successful developments relating to distribution and/or transmission assets undertaken in one part of the business will equally apply to the other. In line with this, costs have been split against each licence based on the turnover and hence size of each network area.

Cost Breakdown between Licence Areas										
Licence Area	Annual Turnover (08/09)	Percentage Split Distribution	Percentage Split Transmission							
SP-Distribution	£315.21 million	~60%	NA							
SP-Manweb	£186.42 million	~40%	~25%							
SP-Transmission	£179.94 million	NA	~75%							

Projects identified as only applying to one licence, or ones that apply in favour of one, two or all three licences have been scaled accordingly (See Table B3). This is defined when the project inception document is developed.

Programme Management Costs

Internal costs for projects detailed in Appendix D are based on SP's input to a project through meetings, correspondence, trials, etc scaled by the appropriate hourly rate for an individual's grade. Programme management is provided by 1x FTE and external contract resource, applied equally across all projects.

Net Present Value (NPV) source

It is noted that IFI projects address a range of issues, and the benefits achieved, and those accounted for in the NPV can be categorised into the following areas:

- Avoided cost A successful development may negate the need to spend money on network components. As an example the development of a high capacity circuit, would avoid the need for duplicate traditional circuits for a given network application.
- Direct savings Successful development could result in a direct financial benefit, e.g. through reductions in operating costs, reduced exposure to Regulatory penalties, etc.
- Managing risk A successful development would assist in reducing the risk profile of the company, either through greater understanding of causes / effects of actions on, or as a result of, network operation (equipment failure, etc.)
- Strategic These projects impact on the longevity of the network, either through external influences such as changes in load / generation patterns, the impact of climate change or even skills / resources.

NB. Whilst an NPV calculation if possible for any project, and across any of these areas, it is recognised that as the assessment looks further to the future (as is the case for strategic projects), the benefits are more susceptible to risk, more uncertain, and consequently less robust.



As of 31st March 09 the status of the 38 projects reported as well as those that have stopped is detailed below.

IFI Pro	ect Status		
No.	Phase	Definition	External Cost
2	Proposals in development	Agreeing scope / objectives, setting up contracts, etc.	None Direct (small external £ associated with management cost)
33	Live projects	Projects in progress	Yes (if milestones have been met)
5	Completed projects	Projects which have completed their trial phase	Yes

This breakdown accounts for reasons why not all projects have significant external spend.

Project Progress Curves

Expenditure profiles are described below to give an appreciation of costs that will be required prior to a project realising a stated benefit through the development cycle. Figure B1 shows a hypothetical expenditure profile for a development project. Expenditure is defined as:

- External Money paid to 3rd parties for work (consultancy, purchase of equipment, monitoring, etc)
- Internal SP Energy Networks' staff time on eligible IFI development work multiplied by the appropriate hourly rate. The success of a project is highly dependent on the levels of internal support a project is given.
- Overall investment The total cost of a project (predominantly external cost) of which the company is accessing through collaborative or external funding leverage. This is the combined investment from SP Energy Networks and other collaborative partners.

In line with sound project management, all IFI projects have been staged into milestones, i.e. the R&D provider will only receive payment upon successful completion of a defined stage.




Figure B1: Example Expenditure Profile for an IFI Project



Table B1 and B2 are ordered chronologically.

Table B1: Overview of 08/09 projects showing application between licences

Project Description		Percentage split		SPD			£ split SPM			SPT					
, ,	SPD	SPM	SPT	ı	External		nternal	E	xternal		nternal	Exte	ernal	lı	nternal
IFI 0401 - Strategic Tech Prog	60%	40%	0%	£	114,812	£	16,687	£	76,541	£	11,125	£	-	£	-
IFI 0402 - LV Voltage Regulator	60%	40%	0%	£	9,562	£	5,258	£			3,505	£	-	£	
IFI 0404 - Alternative Insulating Oil Proje	60%	40%	0%	£	14,824	£	3,033	£	9,883		2,022	£	-	£	-
IFI 0406 - Fault Passage Indication / GSM c	60%	40%	0%	£	39,950	£	10,888	£	26,633	£	7,259	£	-	£	-
IFI 0409 - LV Fault Location devices	60%	40%	0%	£	6,428	£	5,928	£	4,285	£	3,952	£	-	£	-
IFI 0502 - Fault Level Monitor Project	60%	40%	0%	£	824	£	2,484	£	549	£	1,656	£	-	£	-
IFI 0505 - Supergen V	60%	40%	0%	£	15,824	£	2,292	£	10,549	£	1,528	£	-	£	-
IFI 0507 - Smart Dust	60%	40%	0%	£	50,324	£	15,008	£	33,549	£	10,005	£	-	£	_
IFI 0508 - Redox Energy Storage	60%	40%	0%	£	4,029	£	1,872	£	2,686	£	1,248	£	-	£	-
IFI 0509 - Superconducting Fault Current Li	60%	40%	0%	£	21,599	£	3,195	£	14,399	£	2,130	£	-	£	_
IFI 0510 - Alt 11kV Prot	0%	100%	0%	£	-	£	-	£	61,180	£	9,768	£	-	£	-
IFI 0511 - ACTIV Voltage Control	60%	40%	0%	£	25,818	£	7,910	£	17,212	£	5,273	£	-	£	_
IFI 0513 - Thermal State Estimation	60%	40%	0%	£	12,778	£	10,200	£	8,518	£	6,800	£	-	£	-
IFI 0515 - Power Networks Demonstration Centre	60%	40%	0%	£	20,007	£	2,101	£	13,338	£	1,401	£	-	£	_
IFI 0526 - PD Monitoring of Cables	60%	40%	0%	£	12,734	£	3,717	£	8,489	£	2,478	£	-	£	-
IFI 0532 - AURA - NMS	60%	40%	0%	£	108,895	£	23,574	£	72,597	£	15,716	£	-	£	-
IFI 0535 - Radiometric Arc Fault Loctn	60%	40%	0%	£	12,792	£	7,322	£	8,528	£	4,882	£	-	£	-
IFI 0540 - MANtIS	60%	40%	0%	£	1,139	£	2,673	£	759	£	1,782	£	-	£	-
IFI 0607 - LV Automation	60%	40%	0%	£	40,424	£	20,372	£	26,949	£	13,581	£	-	£	-
IFI 0615 - SP Advanced Research Centre	60%	40%	0%	£	87,605	£	3,440	£	58,403	£	2,294	£	-	£	_
IFI 0618 - Supergen 1 - Flex Net	60%	40%	0%	£	24,824	£	1,718	£	16,549	£	1,146	£	-	£	-
IFI 0619 - Advcd Cabling Technologies Prog	60%	40%	0%	£	7,331	£	6,118	£	4,887	£	4,078	£	-	£	
IFI 0620 - Tower Foundation Assmnt DevTrail	0%	60%	40%	£	-	£	-	£	4,907	£	2,335	£	3,271	£	1,556
IFI 0621 - Energy Innovation Centre	60%	40%	0%	£	824	£	1,718	£	549	£	1,146	£	-	£	-
IFI 0624 - Met Office Climate Change Ph2	40%	40%	20%	£	698	£	2,017	£	698	£	2,017	£	349	£	1,008
IFI 0625 - Vegetation Management Project	60%	40%	0%	£	60,224	£	2,550	£	40,149	£	1,700	£	-	£	-
IFI 0628 - Asset Decisn Support Dashboard	60%	40%	0%	£	28,591	£	4,302	£	19,061	£	2,868	£	-	£	-
IFI 0701 - ENA De-minimis Rapper	60%	40%	0%	£	2,305	£	1,718	£	1,537	£	1,146	£	-	£	-
IFI 0702 - Lattice Tower Protective Coat	0%	30%	70%	£	-	£	-	£	2,157	£	446	£	19,415	£	4,013
IFI 0704 - 4E Comms Cooling	0%	10%	90%	£	-	£	-	£	1,744	£	451	£	15,692	£	4,056
IFI 0706 - Ashton Hayes Microgrid Devel.	60%	40%	0%	£	26,924	£	3,087	£	17,949	£	2,058	£	-	£	-
IFI 0707 - Wind Turbine Effects-Trans L	0%	0%	100%	£	-	£	-	£	-	£	-	£	22,615	£	17,533
IFI 0708 - Health Indices for Ast Mgmt DM	60%	40%	0%	£	27,224	£	7,841	£	18,149	£	5,227	£	-	£	-
IFI 0709 - Network Monit using Web Sys	35%	35%	30%	£	8,767	£	2,516	£	8,767	£	2,516	£	7,515	£	2,157
IFI 0710 - GBSQSS Review Studies	0%	0%	100%	£		£	-	£	-	£	-	£	10,707	£	3,502
IFI 0711 - 3rd Party ROEP Risk Assessment	35%	35%	30%	£	1,426	£	1,560	£	1,426	£	1,560	£	1,222	£	1,338
IFI 0712 - BT21 CN Solutions	50%	50%	0%	£	34,516	£	15,265	£	34,516	£	15,265	£	-	£	-
IFI 0801 - IEC 61850 Applications in SPT	0%	0%	100%	£		£		£	-	£	-	£	37,333	£	15,589

	SPD				SPM				SPT				
Totals		External		nternal	Е	xternal		nternal		External	_	nternal	
	£	824,023	£	198,367	£	634,471	£	152,364	£	118,118	£	50,752	
Ratios		81%		19%		81%		19%		70%		30%	



Table B2: Project NPVs, split between licences

Do to a Double	Pero	entage	split		Projec	t NPV		
Project Description	SPD	SPM	SPT	Total NPV	SPD	SPM	SPT	
IFI 0401 2 - STP Module 2 - Overhead Networks	60%	40%	0%	£64,624	£38,774	£25,850	£0	* See Not
IFI 0401 3 - STP Module 3 - Cable Networks	60%	40%	0%	£87,318	£52,391	£34,927	£0	* See Not
IFI 0401 4 - STP Module 4 - Substations	60%	40%	0%	£67,777	£40,666	£27,111	£0	* See Not
IFI 0401 5 - STP Module 5 - Distributed Generation	60%	40%	0%	£89,367	£53,620	£35,747	£0	* See Not
IFI 0402 - LV Voltage Regulator	60%	40%	0%	£45,198	£27,119	£18,079	£0	
IFI 0404 - Alternative Insulating Oil Project	60%	40%	0%	£98,922	£59,353	£39,569	£0	
IFI 0406 - Fault Passage Indication / GSM	60%	40%	0%	£297,916	£178,750	£119,166	£0	
IFI 0409 - LV Fault Location devices	60%	40%	0%	£349,240	£209,544	£139,696	£0	
IFI 0502 - Fault Level Monitor Project	60%	40%	0%	£92,045	£55,227	£36,818	£0	
IFI 0505 - Supergen V	60%	40%	0%	£46,609	£27,965	£18,644	£0	
IFI 0507 - Smart Dust	60%	40%	0%	£554,500	£332,700	£221,800	£0	
IFI 0508 - Redox Energy Storage	60%	40%	0%	£243,753	£146,252	£97,501	£0	
IFI 0509 - Superconducting Fault Current Limiter	60%	40%	0%	-£267,191	-£160,315	-£106,876	£0	
IFI 0510 - Alt 11kV Prot	0%	100%	0%	£50,000	£0	£50,000	£0	
IFI 0511 - ACTIV Voltage Control	60%	40%	0%	£67,445	£40,467	£26,978	£0	
IFI 0513 - Thermal State Estimation	60%	40%	0%	£301,867	£181,120	£120,747	£0	
IFI 0515 - Power System Demonstration Network (PSDN)	60%	40%	0%	£709,171	£425,503	£283,668	£0	
IFI 0526 - PD Monitoring of Cables	60%	40%	0%	£108,661	£65,197	£43,464	£0	
IFI 0532 - AURA - NMS	60%	40%	0%	-£364,068	-£218,441	-£145,627	£0	
IFI 0535 - Radiometric Arc Fault Loctn	60%	40%	0%	£45,787	£27,472	£18,315	£0	
IFI 0540 - MANtIS	60%	40%	0%	£0	£0	£0	£0	
IFI 0607 - LV Automation	60%	40%	0%	-£31,000	-£18,600	-£12,400	£0	
IFI 0615 - SP Advanced Research Centre	60%	40%	0%	£0	£0	£0	£0	
IFI 0618 - Supergen 1 - Flex Net	60%	40%	0%	£0	£0	£0	£0	
IFI 0619 - Advcd Cabling Technologies Prog	60%	40%	0%	£90,726	£54,436	£36,290	£0	
IFI 0620 - Tower Foundation Assmnt DevTrail	0%	60%	40%	£14,220	£0	£8,532	£5,688	
IFI 0621 - Energy Innovation Centre	60%	40%	0%	£0	£0	£0	£0	
IFI 0624 - Met Office Climate Change Ph2	40%	40%	20%	£0	£0	£0	£0	
IFI 0625 - Vegetation Management Project	60%	40%	0%	£681,000	£408,600	£272,400	£0	
IFI 0628 - Asset Decisn Support Dashboard	60%	40%	0%	£163,235	£97,941	£65,294	£0	
IFI 0701 - ENA De-minimis Rapper	60%	40%	0%	£255,876	£153,526	£102,350	£0	
IFI 0702 - Lattice Tower Protective Coat	0%	30%	70%	£1,600,000	£0	£480,000	£1,120,000	
IFI 0704 - 4E Comms Cooling	0%	10%	90%	£905,595	£0	£90,560	£815,036	
IFI 0706 - Ashton Hayes Microgrid Devel.	60%	40%	0%	£7,549	£4,529	£3,020	£0	
IFI 0707 - Wind Turbine Effects-Transmission Lines	0%	0%	100%	£835,466	£0	£0	£835,466	
IFI 0708 - Health Indices for Ast Mgmt DM	60%	40%	0%	£0	£0	£0	£0	
IFI 0709 - Sub.net monitoring	35%	35%	30%	£0	£0	£0	£0	
IFI 0710 - GB SQSS Review Studies	0%	0%	100%	£0	£0	£0	£0	
IFI 0711 - 3rd Party ROEP Risk Assessment	35%	35%	30%	£15,562	£5,447	£5,447	£4,669	
IFI 0712 - BT21CN Protection Solutions	50%	50%	0%	£951,763	£475,882	£475,882	£0	
IFI 0801 - IEC 61850 Applications in SPT	0%	0%	100%	£1,044,386	£0	£0	£1,044,386	

^{*} Note - NPV calculated by external company

	Total NPV	SPD NPV	SPM NPV	SPT NPV
Overall NPV	£9,223,319	£2,765,124	£2,632,951	£3,825,244



Appendix C – Methodology for NPV calculations in IFI projects



Introduction

SP Energy Networks utilises a slightly different approach in the calculation of Net Present Value (NPV) to that described in Engineering Recommendation G85 Issue 2. For transparency, this methodology is outlined below.

In all IFI projects the expected benefits are defined at the outset of the project. In the case of financial benefits the standard business approach is the Net Present Value (NPV) calculation, giving a quantitative representation of the financial benefits that the new technologies will bring verses the cost of the development. As R&D is naturally higher risk than more traditional projects there are many factors, which need to be carefully considered at a projects outset. As a result, the standard NPV assessment approach must be altered to reflect this.

General Methodology

Risk can be factored into an NPV calculation in two ways, with both achieving similar results:

- Applying a variable discount rate
- Using a separate multiplying factor to reduce the benefits.

In line with guidance from Ofgem, our NPV calculations utilise a fixed 6.9% discount rate in line with the agreed cost of capital for the SP-Distribution and SP-Manweb licences in DPCR4 (this rate is also used for SP-Transmission). We therefore introduce risk as a separate factor, the Probability of Success to scale the benefits of each project, as described in the equation below.

$$NPV = \sum_{t=0}^{N} \frac{ct}{\left(1+i\right)^t}$$

 $C_r = (Benefit - Adoption Expenditure) \times PoS - Development Expenditure$

t time (in years) that cash has been invested in the project

N the total length of the project (in years)

i the cost of capital and

C_t the cash flow at that point in time

PoS the probability of successful development

Aside:

Benefit – Cash benefits for at a point in time

Adoption expenditure – Adoption expenditure at a point in time

Development expenditure – Development expenditure at a point in time

The NPV, and in particular, the C_t factor is calculated is as follows:

- The cost of development will always be a direct cost, as the money will be spent if the project goes ahead there is a PV associated with this figure.
- Benefits in the development phase are scaled by the probability of success, as benefits are possible in the development phase, but these will only be realised if the development work is successful.

Both benefits and expenditure in the adoption phase are scaled by the probability of success of development; as expenditure will only occur in the adoption phase if the development work is successful. Similarity the benefits in the adoption phase show the same dependence on successful development.



Phasing

It is noted that if the NPV were taken on solely the development phase of a project, many projects would not commence. This is indicated in Figure C1, where, even by showing the development phase split into two: feasibility and pilot, the magnitude of rollout in the pilot is generally too low to re-coup the original development costs (which can be high). Assumptions on this uptake therefore need to be identified into the adoption phase to ensure a credible result.




Figure C1: How project NPV changes over the course of its development

Cost Assumptions

The costs of an IFI project for the purposes of the NPV calculation can be complicated to quantify, often relying on a number of assumptions. As a minimum, the following are considered:

Development Costs

Cost to develop a product / service / etc

- Purchase of equipment (e.g. necessary equipment to commence the trial, e.g. units for trial)
- Internal cost to project manage and steer

 Anticipated rollout across network
- Cost of installation (equipment, manpower, etc)

Adoption Costs

- Anticipated product unit cost
- Anticipated installation cost

Benefit Assumptions

Benefits too can come in a variety of manners. In some cases a direct financial saving between an existing solution and technology solution may be possible, but in others we must consider more complex mechanisms such as:

- the balance between CAPEX reductions and increasing OPEX (for communications)
- the companies exposure to risk, be that Regulatory or Statutory (CI/CML, environmental or the impact on safety, etc)
- improved understanding and targeting of investment.

Duration of Benefit

The NPV for IFI projects considers projects beyond the traditional development phase and into adoption. In order to measure similar projects this has been simplified as:

- Current carrying Plant (e.g. cables, overhead lines, switchgear) 20-year asset life
- Auxiliary Plant (e.g. protection equipment, comms, etc) 10-year asset life
- Tools & Equipment (e.g. portable fault location equipment, etc) 5-year asset life



Probability of Success (PoS)

The Probability of Success is applied as a scaling factor to all expected benefits during the development phase of a project, and can consequently, have a significant impact on the financial assessment. In order to give a level of consistency to the application of PoS figures, we link our project Probabilities of Success to the concept of Technology Readiness Levels (TRLs). See Table C1.


Technology Readiness Levels (TRLs): Provide a clear indication of how far a product may be from commercialisation. TRLs were first conceived by NASA and are much used in military R&D as a way of gauging a projects status and therefore risk by indicating how far a technology development may be from adoption. Company Resource Likelihood of TRL Definition Networks Interpretation (time / €) Success (adoption) Basic principles observed and Blue skies research 2% reported Applied research (research to address a Technology concept and/or application formulated network related problem or issue) Analytical and experimental critical Bench-top testing phase of a research function and/or characteristic proof of 10% concept. Technology component and/or basic Component lab testing phase of a research 25% technology sub-system validation in lab environment. Technology component and/or basic Connectivity and successful operation of 5 sub-system validation in relevant 35% products in a 'network' lab environment Technology system/subsystem Successful equipment type testing (e.g. 6 model or prototype demonstration in 50% independent HV test lab) a relevant environment Technology system prototype One-off system integration testing with demonstration in an operational 75% installation on live electricity network environment. Actual technology system completed and qualified through test and Widespread network trial 90% demonstration Technology System "qualified" Trial completion: Development of. business 9 100% through successful mission case, application documents, etc operations.

Table C1: Technology Readiness Level / Probability of Success Definition

Figure C2 show diagrammatically, the likelihood of obtaining benefits from a project to its stage of development and probability of success. It is noted that this assessment is a simplification, as it does not fully consider some of the non-linear steps, e.g. from TRL 6 – TRL 7, a commonly expensive transition, which can make/break a project.

It is important to note that the TRL and PoS used in the NPV will be based solely upon assumptions at the outset of a project. As IFI is a mechanism to encourage technological developments, projects will naturally be driven up the TRL scale (with a rising PoS) as they progress to trial and demonstration (specific information in project TRLs is given in Appendix D). However, in the interests of efficiency, the NPV calculation will not be revisited during the development phase.





	TR	L Deve	elopm	ent (St	art –	Currer	nt)	
1	2	3	4	5	6	7	8	9
	→						→	

Figure C2: Relationship between Technology Readiness Level and Probability of Success

The PoS has a significant bearing on the NPV assessment, as projects with a low TRL will give rise much lower, and in some cases negative, NPVs if the development costs are high, and the roll out is conservative. We believe this to be in line with the true spirit of IFI, demonstrating that risk is being taken in areas where without such a recovery mechanism, these developments would have been seen as too risky for a Regulated business to undertake. By way of example, the AuRA-NMS project starts from a low TRL, and hence low probability of success (for the case study we have identified this and translates as a negative NPV).

Successful development of this project would also open up the options to deploy such a system to more applications, further improving the scope for benefits.

Probability of Adoption (PoA)

In all cases for the NPV calculations, there is an assumption that once developed, the technology will be adopted. However, R&D is inherently speculative in nature and only a small fraction of projects developed will actually be adopted within an organisation, this being dependent on a range of factors such as:

- Scale / cost of Rollout
- Complexity
- Regulatory opportunities / barriers (Revenue / Penalties)
- Legislative barriers

All NPV assessments will be revisited and improved prior to adoption. Any lessons learnt will feedback into our NPV methodology outlined above. Although a figure has not been applied to the NPV calculations, it is recognised that only 10%-20% of successfully developed projects are likely to be implemented.



Appendix D – Project Reports IFI Projects April 08 – March 09



Project Title	IFI 0402 - Single Phas	e LV Vo	oltage Reg	ulato	ors						
Description of project	Development of a sin into a LV line to prov voltages effectively m	ide fas	t response	e volt	age co	mpensa	ation fo	-			
	Internal £8,763	3	Expenditu	ıre in		Int	ernal		£32,2	L24	
Expenditure for financial year	External £15,93		previous (nancia	I Ext	ernal		£172	,958	
iniancial year	Total £24,6 9	99	years			To	tal		£205	,082	
Project Cost				/-	_	_	ernal		£0		
(Collaborative +	c£250,000		Projected for SPEN	09/1	0 costs	Ext	ernal		£0		
external + SPEN)			101 01 211			To	tal		£0		
Technological area and / or issue addressed by project	It is envisaged that th complaints in rural ar		ce will prin	narily				apidly	y resolv	ring vo	oltage
Type(s) of	Incremental	S	ignificant			echnolo ubstitu			Ra	dical	
innovation involved	No		No			Yes				No	
Expected Benefits of Project	Where there is a cle engineer the most co the complaint whilst construction undertal. Where the voltage coprovide a permanent sags.	st effec a reinf ken. omplair	tive soluti forcement nt is due t	on, the sche	ne volta me is curbing	age reg designe	ulator o ed, way or unid	ould -leav	be used es nego ed cau	d to re otiate ses it	esolve d and could
Expected Timescale to adoption	<1 Year		Duration achieve		enefit	once			10 Yea	rs	
Doob ability of				TI	RL Dev	elopme	nt (Star	t – Cı	urrent)		
Probability of Success	50%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pr Costs	robabili	ity of Succ	ess) –	- Prese	nt			£45,19	98	
Project Progress March 09	The regulators have are installed tempora					-					some
Potential for achieving expected benefits	This project will be closed in the 2009/10 period, with the use of the regulator being brought into line with SPEN's reinforcement policy										
Collaborative Partners	Phase 1(development Phase 2 (trial): Electri	-		Scotti	sh & S	outherr	n Energ	/			
R&D Provider	MicroPlanet USA (LV	Regulat	tor), GMC	Instru	ıments	(monit	oring)				



Project Title	IFI 0404 - Alternative	Insulatin	g Oils – Phase	2 1							
Description of project	Applied research prog thorough evaluation of aged power transforn	of the ele	ctrical/ageing			_		_			
	Internal £5,0	54	Expenditure	in		Intern	al	£8	,487		
Expenditure for financial year	External £24,	707	previous (IF		icial	Exterr	nal	£2	9,512		
maneral year	Total £29,	761	years			Total		£3	7,999		
Project Cost						Intern	al	£3	,000		
(Collaborative +	£142,290		Projected 08 for SPEN	3/09 cc	osts	Exterr	nal	£1	6,400		
external + SPEN)						Total		£1	9,400		
Technological area and / or issue addressed by project	relative merits for Re	valuation of the Characteristics of Alternative Oils is being undertaken to access the elative merits for Retro-Filling Power Transformers and filling New Transformers with Iternative oils have over using standard mineral oils.									
Type(s) of	Incremental	Sig	nificant		echnol ubstitu	_		Ra	dical		
innovation involved	No		No		Yes	i			No		
Expected Benefits of Project	 Reduced environ Potential to up-ra Opportunity to ir reputation with r 	ate transf nprove SI	ormers at stra PEN credibility nvironmental	ategic s with awarei	sites. SEPA a ness.		er gov	erning/	bodie	s and	
Expected Timescale to adoption	4 years		Duration of once achiev	ed				20 years			
Probability of	50%		1 2 T	RL Dev	elopm/ 4	ent (Sta	art – (6	Current) 7	8	9	
Success	3070		1 2	3	4		<u> </u>	,	0	9	
Project NPV	(Present Benefits x Pr Costs	robability	of Success) –	Prese	nt		1	£98,922	2		
Project Progress March 09	 Introduction of p rising. PDIV of surface d However, in high Relationship in brare: Mineral oil > When gap is smapressboard can h becomes more ol 	 PDIV of bulk oil and surface discharge in FR3 or Midel are almost the same. Introduction of pressboard speeds up the increase of PD magnitude with voltage rising. PDIV of surface discharge in FR3 is lower than that in Midel. However, in higher voltages, PD magnitudes in Midel are always higher than in FR3. Relationship in breakdown voltages of three oils for both bulk oil and surface tests are: Mineral oil > FR3 > Midel When gap is small, difference in breakdown voltages between with and without pressboard can hardly be observed. However when gap is larger, difference becomes more obvious. 									
Potential for achieving expected benefits										It is work vithin sites int of these	



	 collaborative partners in order to gain confidence in their application. Results of testing are so far proving positive with regards to using Midel oil in large power transformers.
Collaborative Partners	National Grid, Electricity North West, EDF Energy, Areva T&D, TJH2B, M&I Materials
R&D Provider	University of Manchester

R&D Provider	University of Manches	ster									
Project Title	IFI 0406 - Overhead Li	ine Fau	ılt Pas	sage In	dicato	rs					
Description of project	The development of communications to m the 33kV and 11kV ov	easure	and r	ecord t							
Expenditure for financial year	Internal £18,14 External £66,58 Total £84,72	33	-	nditure inancial	-	/ious	Interr Exterr Total		£	28,046 131,81 159,85	2
Project Cost (Collaborative + external + SPEN)	£329,794		Proje SPEN	cted 08	/09 co	sts for	Interr Exterr Total		£	5,000 35,000 40,000	
Technological area and / or issue addressed by project	Implementing a recommunications for unisolation of faults.				_					eless locatio	
Type(s) of	Incremental	S	Signific	ant		Techno substi	_		F	Radical	
innovation involved	Yes		No			N	0			No	
Expected Benefits of Project	 Fault indicators vimproving responsions This project focus Reduced damage service benefits, vimproving responsions 	nse time ses on i e to la	e and s reducir nd thr potent	subsequing restorough u	ient re ration innece roved p	estoration time to essary a percept	on of su o rural o occess.	pplies custom This	to cus ners. also h	tomers	
Expected Timescale to adoption	<1year		Durat	ion of b	enefit	once			10 yea	rs	
Probability of Success	50% - Apr 07 75% - Apr 08	-	TRL D	evelopi 2	ment (Start – 4	Current 5	6	7	8	9
Project NPV	(Present Benefits x Pro Costs	obabili	ty of S	uccess)	– Pres	ent		f	297,91	L6	
Project Progress March 09	(Present Benefits x Probability of Success) – Present Costs Commenced in January 2008 with an analysis of the project to date, and a re-evaluation of the project direction. Throughout Stage 3, the following technology was purchased and trialled: - 48 Bowden Brothers Pathfinder 360 Alpha FPIs, permanent pole-mounted - 48 Nortech Management Polestar NX FPIs, permanent pole-mounted - 24 FMC Tech Crystal Systems, conductor-mounted - iHost Server space being rented - 6 Nortech Management NX11 Power Outage Detectors - 60 Bowden Brothers Rightway Mark 10 FPIs, portable pole-mounted To date the following results have been obtained										



	Pathfinder 260 Alpha EDI was the most assurate entire for permanent attachment
	- Pathfinder 360 Alpha FPI was the most accurate option for permanent attachment. Their average accuracy was shown to be 92% after 17 faults.
	- The Polestar NX FPI was shown to be accurate 51% of the time after 18 faults.
	 The conductor-mounted Crystal Systems never operated or connected to iHost consistently to prove worthwhile.
	- The Rightway Mark 10 portable FPIs were shown to be a flexible and effective tool
	for the zones as long as they were used proactively.
	- The NX11 Power Outage Detectors were 100% accurate after 1 fault.
	, and the second
	The data collector, iHost, was shown to be effective at collecting information from many
	different types of unit and displaying it in an easily interpretable consistent manner.
	The objectives of the project were to ascertain what communicable FPI technology was
	available on the market for the overhead network, which was the most effective and
	how best to use the information reported.
	·
Potential for	These objectives were met fully and the conclusions were that the Bowden Pathfinder
achieving expected	360 Alpha was the most effective permanent pole-mounted FPI. The best way to use
benefits	the information was to collect it with the iHost server and, depending on the end user,
	to either display it on a web page or to route it directly into the control program.
	to outlier display it on a ross page of to route it amount mite the control programm
	This project is due to be closed in August 2009
Collaborative	
Partners	N/A
raitiicis	Pole Mounted Pavises: Nortech Pouden Pres
R&D Provider	Pole Mounted Devices: Nortech, Bowden Bros.
	Conductor Mounted Devices: FMC Tech

Project Title	IFI 0409 - LV Fault	Location Dev	vices									
Description of project		device for use on the Low Voltage networks to capture transient fault information and relate to an associated fault location.										
	Internal f	9,880			Internal	£24,790						
Expenditure for financial year	External f	10,714		liture in previous ancial years	External	£69,589						
	Total £	20,593	(,	arrorar y care	Total	£94,379						
Drainet Cost					Internal	£7,100						
Project Cost (Collaborative +	£184,80	00	Projected 08/09 costs for SPEN		External	£20,000						
external + SPEN)			3. 2.1		Total	£27,100						
Technological area and / or issue addressed by project	The device is be location.	ing develope	d prelim	inary for transient/i	ntermittent L	.V cable fault						
Type(s) of	Incremental	Signific	cant	Technological substitution	Ra	adical						
innovation involved	No	Yes	5	No		No						
Expected Benefits of Project	Preliminary use of the device for fault location on persistent LV faults is expected to: Reduce the number of repeated fuse replacements Minimise the number of joint holes Remove the fault from the system in a shorter timescale than traditional 'cut-and test' methods											



Expected Timescale to adoption	1 Year Duration of benefit once achieved Typically 8-10 years depending on technology developmen										
			٦	ΓRL Dev	elopmen	t (Sta	rt – Cı	urrent))		
Probability of Success	50%										
								<u> </u>	\geq		
Project NPV	(Present Benefits x Probability o	(Present Benefits x Probability of Success) – Present Costs £349,240									
Project Progress March 09	 Embedded into iHost the than from base station. iHost has been brought int records which enables info 	o line	with b	ase stat	ion softv	vare t					
Potential for achieving expected benefits	 Collaboration with ENW to embed software into iHost Develop TP22 further to communicate whilst monitoring (sending fault record back while recording fault incident) Automate fault location process as far as possible 										
Collaborative Partners	Phase 1: N/A; Phase 2: EDF-Energy; Electricity North West										
R&D Providers	Kehui (UK) Ltd, Nortech										

Project Title	IFI 0502 - Fault Level I	Monitor Pro	ject							
Description of project	An ENA co-ordinated instrument that can network with repeata	successfully	/ measui		-					
Expenditure for financial year	External £1,	Expenditure in previous (IFI) financial years Expenditure in previous External £13,237								
Project Cost (Collaborative + external + [DNO])	£190,000	#190,000 Projected 09/10 costs for SPEN Internal £4,000 External £30,550 Total £34,550								
Technological area and / or issue addressed by project	The device will conne from small-scale distr operation, etc. This level for that locatio planning engineers ali	urbances / p impedance n, providing	erturbat can accu	ions resulting from rately be correlated	transfo	ormer t true ne	cap changer etwork fault			
Type(s) of	Incremental	Signific	ant	Technological substitution		F	Radical			
innovation involved	No	Yes		No			No			
Expected Benefits of Project	 The developed unit will allow the DNOs to accurately assess fault infeed levels and design distribution networks appropriately. The particular benefits of this project are seen to be: Provide a real-time and consistent estimation of fault level Accurately take into account all connected network elements (e.g. Motors); Facilitate the connection of distributed generation by providing a standardised methodology for the assessment of network fault levels Enable an ongoing assessment of the effects of connected distributed generation to be made; 									



	Provide reassurance to generator developers that decisions to upgrade networks are not subjective but based on objective measurement.										
Expected Timescale to adoption	3 years	Duration of benefit once achieved						10 years			
Probability of Success		TRL Development (Start – Current)									
	25%	1 2 3 4 5					6	6 7 8 9			
Project NPV	(Present Benefits x Probabilit	ity of Success) – Present Costs £92,045									
Project Progress to March 09	The results of the tests carried out at NaREC show that the EA Technology Fault Level Monitor is capable of delivering an assessment of both the source and motor infeed elements of fault level. The accuracy of the assessment can be delivered with the tolerance levels (+/- 5%) which were set down by ENA OSG sub-group. However, it should be noted that the instrument is based on a hardware platform which is obsolete and no longer supportable. Stage 2 of the previous work carried out in conjunction with the University of Strathclyde, was intended to develop a new Fault Level Monitor. Consideration should be given to the need to carry out further development of a new platform to collect and analyse the disturbance data.										
Potential for achieving expected benefits	The confidence limits in the case of the induction motor infeed assessment were affected by the relatively low number of recorded disturbances and also appear to have been affected by the 'two-stage' nature of many of the disturbances. Further work should be undertaken to examine the effect of the load response of non-linear static loads on the estimate of fault level contribution from induction motors. A PhD studentship at the University of Strathclyde the PNRA to explore this issue is being advertised										
Collaborative Partners		sh & Southern Energy, CE Electric UK, Electricity North West, estern Power Distribution, EDF-Energy Networks									
R&D Providers	University of Strathclyde, EA Technology										

Project Title	IFI 0505 - Supergen V - AMPerES							
Description of project	Supergen is an EPSRC strategic partnership programme incorporating a collection of projects across a number of UK academic establishments. This fifth call, Supergen V is entitled Asset Management & Performance of Energy Systems (AMPerES).							
Expenditure for financial year	Internal	£3,821	Expenditure in	Internal	£7,974			
	External	£26,374	previous (IFI)	External	£77,902			
	Total	£30,194	financial years	Total	£85,876			
Project Cost (Collaborative + external + SPEN)	£ 2,800,000		Projected	Internal	£5,000			
			08/09 costs for	External	£25,000			
			SPEN	Total	£30,000			
Technological area and / or issue addressed by project	WP 1: Programme delivery, outreach and implementation WP 2: Enhanced network performance and planning WP 3: Adaptable protection and control techniques WP 4: Infrastructure for reducing environmental impact WP 5: Ageing mechanisms WP 6: Condition monitoring techniques							



Type(s) of	Radical		ject Be Rating		Р	Project Residual Risk			Overall Project Score			
innovation involved			11			-4			15			
Expected Benefits of Project	 The expected aims of the project are: To deliver a suite of intelligent diagnostic tools for plant To provide platform technologies for integrated network planning and asset management To progress plans to develop and implement improved and reduced environmental impact networks To develop models and recommendations for network operation and management 											
Expected Timescale to adoption	Year 2013		Duration of benefit once achieved 20 Years									
			7	RL De	velopn	nent (St	art – C	1)			
Probability of Success	25%		1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs £150k											
opportunities for condition monitoring is key to optimising performance, financially and in quality of supply. Some of the technologies being developed i programme are likely to be utilised, however much more important is the browning window this work gives to the global research community. Through demonstration the true value of condition monitoring will be identified, enabling appropriate but decisions on adoption of technologies.								n this oader n sites				
Project Progress June 2009	 Technology & trials: The detection, control and protection synchronous islands have been demonstrated on a 50kVA diesel generator. The demonstration employs a real-time phasor measurement system. An AC optimal power flow method for assessing the maximum distributed generation (DG) penetration in distribution networks has been developed. A novel method of detection of loss of grid techniques is being developed. A low-cost system with internet broadcast capability has also been developed: four are currently in operation. An investigation into how regions of a distribution network can operate during emergency islanded mode conditions is also underway. Optimized design of existing overhead lines of wood pole line, and a lattice tower line. The methodology has been employed to analyse the behaviour of low-sag composite conductors on a 33kV wood-pole structure. The model is now being utilised on a wood-pole line on Scottish Power and a lattice tower line on the National Grid, and may substantially improve the performance of sections of the network without major infrastructure changes. A unique installation for transformer monitoring at National Grid comprising of two 275/132kV, 180MVA transformers, is implementing results of research on condition monitoring architectures, diagnostics and machine learning. Development of condition monitoring architecture for power networks has progressed well and is being implemented on a National Grid transmission transformer. Diagnostic and support modules are included, and exploit a range of ageing models including those developed within this project. Work on ageing has shown that the rate of damage may not be affected by harmonic content, but 											



	 PP-based alternatives to XLPE cable insulation have been characterised. Additional funding has been secured for the more applied work to develop routes to commercial exploitation. Vegetable oils have been shown to be a basis for replacement of mineral oils in HV equipment. Strathclyde and Liverpool have been applying knowledge-based partial discharge analysis and chromatic analysis to data from EdF Energy cable monitoring systems. All publications and reports are available to all the partners from a secure web site: http://www.supergen-amperes.org/
Collaborative	National Grid, Scottish Power, Scottish and Southern, United Utilities, Western Power
Partners	Distribution, Central Networks, CE Electric, NIE, Advantica & EDF Energy Networks.
R&D Provider	Universities of Manchester, Southampton, Edinburgh, Liverpool, Strathclyde, Queens (Belfast).

Project Title	IFI 0507 - Sensor Netwo												
Description of project	self-configuring wirelest information in a series relayed through a gatew into the use of this teroverhead line networks. Following on from this Energy, Central Network	"Smartdust" is a concept developed by the University of California that is based on a self-configuring wireless sensor network, capable of transmitting low bandwidth information in a series of short hops. Data acquired and transmitted from sensors is relayed through a gateway for data interpretation. ScottishPower led a feasibility study into the use of this technology for detecting the passage of fault currents on 11kV overhead line networks. Following on from this work, a collaborative project has been scoped between EDF-Energy, Central Networks and SPEN to develop a product based on this principle for the remote signalling of fault passage indication on OH networks.											
	Internal £25,014			ernal	£10,257								
Expenditure for financial year	External £83,874	nal £83,874 Expenditure in previous (IFI) financial years											
ililaliciai yeal	Total £108,887	7	Tot	:al	£26,965								
Project Cost	-1			ernal	£7,500								
(Collaborative +	Phase 1 = £16k Phase 2 = £191k	Projected 09/10 c	osts for Exte	ernal	£50,000								
external + SPEN)	PlidSe 2 - E191K	ase 2 = £191k SPEN Total £57,500											
Technological area and / or issue addressed by project	any other option, a	Line Faults would sign etwork and consequently pecially suited to transit as been undertaken of ge Indicators Vs Radio of considering the relation rement to CML figures. based system: her percentage of location cross all price points and gher NPV than any other a significantly higher povices to above 70% cov	nificantly reducy reduce CML ory fault location the deplocommunicating aship between The key concludes of be more time savings or option	uce the tin associated ion. byment ch g sensors, n sensor co lusion is th nitored eco	me required to dipenalties. This aracteristics of using SP-D fault ost, deployment hat a cheap, low conomically than in the monitored of the increasing the								
Type(s) of	Incremental	Significant	Technolo substitu	-	Radical								
innovation involved	No	No	No		Yes								



Expected Benefits of Project	Sensor Networks implemented an enormous effect on how fa have a huge impact on CI/CN pointing faults on the network.	ults or 1L figu	n the o	overhe the t	ad ne echno	twork logy w	are lo ⁄ould	cated. be eff	They	could
Expected Timescale to adoption	5 Years Duration of benefit once achieved 10 Years									
5 1 1 1111			Т	RL Dev	/elopn	nent (S	tart –	Curren	t)	
Probability of Success	50%	1	2	3	4	5	6	7	8	9
						\geq				
Project NPV	(Present Benefits x Probability of Costs	of Succ	ess) –	Presen	t		f	554.5	(
Project Progress March 09	The development of a softwar whilst maintaining radio batter the designer Willow Technological Although a radio based commuterefore power efficient, if it is data relevant to the purpose, to become a power drain. Willow awakened period to conserve purcan enables diverse alternate recommunication.	y life a es. unication to be on the property of the property o	on syst come a ust also devel	tem ge ware o be al oped a	enerall of thos ble to a syste	ated a ly repo se in th receive em tha	rts by ne vicir e trans	excep nity that smissic ses a s	tion, a at may ons and taged	and is have d this radio
Potential for achieving expected benefits	SPEN have selected two trial si circuit having 30 sensors each.	ites, or	ne in e	ach of	the c	distribu	tion li	cences	, with	each
Collaborative Partners	Central Networks									
R&D Providers	Willow, E.ON Power Technology	′								

Project Title	IFI 0508 - Developme	nt of Red	lox flow batter	y for energy st	orage						
Description of project	A part funded project through the TSB Technology Programme TP/3/ERG/6/1/16587(D05/726039) that aims to develop (design, build, test and install) an 11kV 250kW Redox flow battery unit for energy storage.										
Expenditure for	Internal £3,1	21	Expenditure i	n nrevious	Intern	al	£10,493				
financial year	External £6,7	15	(IFI) financial	•	Extern	ıal	£1,144				
, , , , ,	Total £9,8	36	,	,	Total		£11,637				
Project Cost				Intern	al	£3,500					
(Collaborative +	£965,567		Projected 07/ SPEN	Extern	al	£30,000					
external + SPEN)			JF LIN	SI EIV			£33,500				
Technological area and / or issue addressed by project	/ or issue transformers and potential improvements to network performance. Development of a device which can be connected to the 11kV network and provide power by charging										
Type(s) of	Incremental	S	ignificant	Technolog substituti		R	adical				
innovation involved	No		Yes	No			No				



Expected Benefits of Project	stacks which may previously voltage problems exist. By placing these devious Furthermore, a device costly. As a replacement for environmental impact. One of the most significations	 stacks which may prevent the need to upgrade certain parts of the network where voltage problems exist. By placing these devices in the network, voltage problems could be reduced. Furthermore, a device could be employed where providing a supply is difficult or costly. As a replacement for current lead-acid batteries, this technology has a low environmental impact. One of the most significant outcomes expected of this project is the understanding for how storage systems could be connected to the network, and their likely applications. 								
Expected Timescale to adoption	2 Years	2 Years Duration of benefit once achieved 10 Years								
Probability of				TRL De	velopn	nent (S	tart – C	urrent)	
Success	25%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probabil	ity of S	uccess) – Pres	ent Cos	sts	•	f	243,75	3
Project Progress March 09	This project has been put or	n hold i	ndefin	itely du	e to fin	ancing	issues			
Potential for achieving expected benefits	This project has been put on hold indefinitely									
Collaborative Partners	DTI (via Technology Progran Ltd	DTI (via Technology Programme), ESD Ltd, Univ. of Southampton, Econnect, Swanbarton Ltd								
R&D Providers	ESD Ltd (project managers)									

Project Title	IFI 0509 - Su	perconducting F	ault Current Limiter									
Description of project		•	develop and trial three 12kV S ree different UK networks.	uperconductir	ng Fault Current							
E dita f	Internal	£5,325	Europe dita una in consulta un	Internal	£20,543							
Expenditure for financial year	External	£35,999	Expenditure in previous (IFI) financial years	External	£105,245							
	Total	£41,324	(117) manetal years	Total	£125,788							
Project Cost			Drainstad 09/00 sasts for	Internal	£10,000							
(Collaborative +	£2,3	£2,345,967 Projected 08/09 costs for SPEN External £49,187										
external + SPEN)	nal + SPEN) Total £59,18											
Technological area and / or issue addressed by project	When the n resistance, t increased cunitrogen) ca to a normal Being a solid after which (protection fast to ensure current can be a solid current current can be a solid current curr	naterial is opera thereby allowing irrent density can uses the tempera resistive state. I state device, the the impedance re operated circuit re that the first possess to suit a sp	clamping and clearance of fau ted at below its critical temp load current to flow with n used by fault current, or the loature of the superconducting me SFCL has been proven to o emains high until the fault is cl breakers, fuses, etc.). The SF peak of the fault current is lim pecific application. O) will be constructed and in	perature it lossegligible losses of cooling material to rise perate in a feeared by convictly's operationited. The sub	es. Either the medium (liquid se and it reverts ew milliseconds, ventional means on is sufficiently sequent limited							



	applications: transformer tails, bus section, interconnected network connection. The successful completion of this project is likely to pave the way for higher voltage devices.										
Type(s) of	Incremental	Si	gnifica	nt		Technolo substitu	_		R	adical	
innovation involved	No		Yes			No	1			No	
Expected Benefits of Project	11kV fault current limi Successful trials will r are capable of clampi will open up another	To develop, understand and address the issues associated with the connection of an 11kV fault current limiting device to the network. Successful trials will result in the development of commercially available devices that are capable of clamping fault levels to within network design limits. Once proven, this will open up another option for tackling network fault level, potentially providing an alternative to network reinforcement.									
Expected Timescale to Adoption	3 years		Durat achie		benefi	it once			20 ye	ars	
Probability of				7	RL De	velopm	ent (S	tart – (Current	:)	T
Success	25%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pr Present Costs	obabilit	y of Suc	ccess) -	-	_	low T	£-26 PV is ne RL / hig omme	h cost	s upon	
Project Progress March 09	 The first pilot SF commissioning on The cryogenic sys issues have been Work on pilot 2 (S 2009. 	ice ENW item wa mitigate	/ have i is made ed.	ncorpo e opera	orated ational	it into t I in Mar	heir n	etwork ome in	c itial ac	oustic	noise
Potential for achieving expected benefits	 Pilot 1 is expected to go live in summer 2009 and work progresses on pilots 2 and 3 with installations in 2009/2010. The project is managed against milestones and future milestones include the assembly and type testing at an independent test house prior to installation and commissioning of all units. 										
Collaborative Partners	Electricity North West, CE Electric UK, Applied Superconductor Ltd										
R&D Providers	Applied Superconduct	Applied Superconductor Ltd									

Project Title	IFI 0510 - Ini	novative Protectio	n Solutions									
Description of project	scheme for	The aim of this project is to investigate and develop a radio-based directional blocking scheme for use on interconnected ring-type 11kV and 6.6kV networks in the SP-M licence area.										
Evnanditura for	Internal	£9,768	Expenditure in	Internal	£6,833							
Expenditure for financial year	External	£61,180	previous (IFI) financial	External	£2,902							
illialiciai yeai	Total	£70,948	years	Total	£9,735							
Project Cost		n i i logico i Internal £10k										
(Collaborative +	£1	.50,000	Projected 08/09 costs for SPEN	External	£35k							
external + SPEN)			IOI SPEIN	Total	£45k							
	At present t	ne interconnected	I 11kV and 6.6kV networks	are protected	through the use							
Technological area	traditional (unit based scher	nes. However a subset	of these net	works utilise bi-							
and / or issue	directional o	directional overcurrent and earth fault relays at remote primary substations.										
addressed by												
project	Protection tl	Protection theory shows that it is impossible to achieve true time-based discrimination										
	in a solidly	interconnected ri	ng network. In practice, ϵ	experience sho	ws that suitable							



		grading can be achieved, with limitations (such as the use of relatively high time multipliers, and limited deployment around the ring resulting in large protection zones)									
Type(s) of	Incremental	S	ignifica	ant	-	Techno substi	_		R	adical	
innovation involved	No	Yes Yes					es			No	
Expected Benefits of Project	Reducing time multip	Reducing time multiplier, protection clearance times should be improved									
Expected Timescale to adoption	1 year (assuming succestrial)	1 year (assuming successful trial) Duration of benefit once achieved 10 Years									
Probability of		TRL Development (Start – Current)									
Success	75%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Proba Costs	ability o	of Succ	ess) –	Preser	nt			£50,00	00	
Project Progress March 09	 There are two communic Oswestry – Lord Stree Lord Street – Coney The five limb VT's are now order to accept the new V 	et – Mi Green - w in sto	imoma - BT so ock. VT	x radion lution recept	o link h to be tacle a	nas pro trialled ind circ	ļ			th end	s, in
Potential for achieving expected benefits	Protection panel has been design and will be constructed by SPEN fitters. Relays are on order from SEL and should be delivered June/July										
Collaborative Partners	N/A										
R&D Providers	Schweitzer Engineering L	aborato	ories /	FreeW	ave R	adio					

Project Title	IFI 0511 - Volt	IFI 0511 - Voltage Control ACTIV (EATL)									
Description of project	network and to undertake	This project is to investigate active voltage control to increase the efficiency of the network and facilitate the connection of distributed generation. More specifically it is to undertake field trials of the Fundamentals SuperTAPP n+ automatic voltage control (AVC) relay and develop associated modelling criteria for network planners.									
Evnanditura for	Internal	£13,183	Evpanditura in nr	ovious	Internal	£6,188					
Expenditure for financial year	External	£43,030	Expenditure in pr (IFI) financial year		External	£39,177					
interior year	Total	£56,213	(ii i) iiidiidia yedi	3	Total	£45,365					
Project Cost					Internal	£6,000					
(Collaborative +	£254	,206	Projected 08/09 of SPEN	costs for	External	£69,369					
external + SPEN)			SPEN		Total	£75,369					
Technological area and / or issue addressed by project	It is proposed that this relay could provide a viable alternative for voltage control across SP-M / SP-D in areas where the ratios of generation to load is high.										
Type(s) of	Increme	ental	Significant		nological titution	Radical					
innovation involved	Yes		No	No No							



Expected Benefits of Project	 requires minimal netw Improving the voltage Reducing the requiren the capacity for the co Reducing the risk of 	requires minimal network modification; Improving the voltage profile of supply; Reducing the requirement for network extensions or reinforcement and increasing the capacity for the connection of distributed generation; and									
Expected Timescale to adoption	<2 Years	Durat achie	ion of l	oenefit	once			10 Yea	rs		
Probability of			T	TRL De	velopn	nent (S	tart – C	urrent)	ī		
Success	75%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Probab	ility of	Succes	s) – Pre	esent Co	osts		£67,	445		
Project Progress March 09	 Three of the four trial sites are now installed and producing data for validation. These include: A simple landfill generator on an 11kV radial network; A 33kV lightly interconnected network with wind generation; An 11kV radial network with Load Drop Compensation and large amount of generation and varying load types. Over 10,000 operational hours have now been recorded. A number of issues have been discovered and addressed. Desktop studies have been completed on two of the sites and indicate that more voltage headroom for generation can be created with little requirement for additional operator intervention. 										
Potential for achieving expected benefits	The voltage control scheme is operating as expected over a range of operating conditions. It is likely that the expected benefits will be achieved.										
Collaborative Partners	Central Networks, Scottish & Southern Energy, Electricity North West										
R&D Providers	EATL, Fundamentals										

Project Title	IFI 0513 - Thermal modelling and Active Network Management									
Description of project	A part funded project through the Technology Strategy Board (TSB) Technology Programme (TP/4/EET/6/I/22088) that aims to optimise network design, operation and control by exploitation of dynamic circuit ratings.									
	Internal £17,001		Internal	£13,800						
Expenditure for financial year	External £21,296	Expenditure in previous (IFI) financial years	External	£42,976						
, , , , ,	Total £38,297	, , , , , , , , , , , , , , , , , , , ,	Total	£56,776						
Project Cost			Internal	£15,000						
(Collaborative +	£903,000	Projected 08/09 costs for SPEN	External	£71,000						
external + SPEN)			Total	£86,000						
Technological area and / or issue addressed by project	 The ratings given to circuits are a function of the temperature by which they operate. The thermal status of a power system component is determined by factors such as: current flow, meteorological conditions and component heat transfer characteristics. This project seeks to explore the potential benefits arising from: Improved utilisation of power system assets through the use of real time 									



	 knowledge of the thermal status of the power system. Development of an active controller to facilitate this exploitation and to balance those issues requiring action by operational staff and those that can be dealt with by machine intelligence. The result of this work will be a prototype active controller, using novel thermal state estimation and control techniques, installed on the network. 									that	
Type(s) of	Incremental		ficant		Te	chnolo ıbstitu	gical			dical	
innovation involved	No	Y	es			No			No		
Expected Benefits of Project	may be a way o distribution netwo • Improved utilisation	may be a way of accommodating increased levels of renewable generation in distribution networks cost effectively.								on in	
Expected Timescale to adoption	2 Years			ion of achiev	benef ed	it		1	0 Year	S	
				Т	RL Dev	elopm	ent (S	tart – (Curren	t)	
Probability of Success	25%	1	2	3	4	5	6	7	8	9	
Success									>		
Project NPV	(Present Benefits x Pro	bability of	Succe	ss) – F	resen	t Costs			£301	,867	
Project Progress March 09	 IEC standard-base transformers have A thermal state es electric cables and component therm algorithm has bee An algorithm has bee An algorithm has bee forecasted meteor Computational flu overhead lines and power transforme Power flow sensiting generation for net developed and val Joint electro-therm networks Thermal controlled energy yields, importages and a final work has been dis (in press late 2009 conference publications). Hardware for opensite visits at trial soconsiderations. Field trial open-locations. Field trial open-locations. Thermal instrument Hardware for the similar project in Stranger and programme has been disprogramme has been dispro	been development of the undertall of the	eloped lgorith insform mand for own oped the second	and verments of fore the data ave being four the control of the co	alidate been The property I mete ad lines cast control lines cast cast control lines cast cast cast cast cast cast cast cas	ed with development of the and of the end of the ponent of the ponent of the ponent of the end of t	n offline ped for a control of the c	e data or over over over over over over over o	head I e calcuments ratings and val g deve ol of derators osfers, be IET and 7 in l detail	ines, lation The sthrous idated loped stribus have sase study and IMe ternated dware erating oject	of Ifor ted been Idy echE ional sign to a



	multiple MiCOM relays and a high-level host controller.
Potential for achieving expected benefits	The equipment needed for the open loop field trials. Network data is presently being gathering from the instrumented network and Open loop trials of the TSEA and control algorithm are expected to begin in June 09.
Collaborative Partners	TSB (via Technology Programme), Durham University, Imass, Areva T&D, PB
R&D Providers	PB (project manager), as above

R&D Providers	PB (project manager),	as above							
Project Title	IELOE1E Bower Cont	am Domanstration Co	ntro (BNDC)						
Project Title Description of project	Development of a fu ground for active net Whilst not a technolo technology, with sig	em Demonstration Central scale 11kV and LV property work management tectorical development in inficant potential to a range of IFI projects	prototyping nathriques and tself, this proaccelerate accelerate	other 'high oject is a fun	risk' technologies. damental enabler of				
Expenditure for financial year	Internal £3,5 External £33, Total £36,	Internal External Total	£26,711 £23,450 £50,161						
Project Cost (Collaborative + external + SPEN)	£7,200,000	Projected 0 for SPEN	8/09 costs	Internal External Total	£10,000 £42,500 £52,500				
Technological area and / or issue addressed by project	 Provide a demondary real network Offer a real network Offer a real network Create a facility Manufacturers, at The vision is to cresult of the vision and rural network components control equipment, in thing. Real Time Dunderlying, more consystem. Technologies coming 	 Offer a real network that will incorporate 11kV and low voltage equipment, containing real loads, real generation and test real technologies Create a facility which will be open to Academia, R&D Establishments, Manufacturers, and Network Operators The vision is to create a physical scale model that can represent different urban, suburban and rural electrical networks. The proposed system will incorporate real network components: cables, overhead lines, switchgear, transformers, protection and control equipment, in order to ensure it is both representative and credible to the real thing. Real Time Digital Simulators (RTDSs) will be used in parallel to model an underlying, more comprehensive network, effectively expanding the scale of the 							
Type(s) of	Incremental	Significant	Technol substit	logical	Radical				
innovation involved	Yes	Yes	Ye	es .	Yes				
Expected Benefits of Project	Benefits to DNOs from such a facility include: Safety — A test network with dedicated staff will offer a facility to train staff in the operation of a more complicated network. Specific what-if scenario courses can be run through repeatable simulation, in the same manner as flight simulators are used to train pilots. Risk mitigation — A real time simulator, with likely penetrations of high volume DG and microGen will indicate the technologies that will need to be developed in order to manage the increased risk this might pose to the network and/or our customers. Acceleration of trials / increased adoption rate — The ability to operate the whole network through a vast range of loading conditions in a short period of time, will lead to the end of long duration (12-24mth) network trials of new technologies.								



		1									
Expected Timescale to adoption	3 Years	Duration of benefit once achieved 20 Years									
				TRL De	velopn	nent (S	(Start – Current)				
Probability of Success	25%	1	2	3	4_	5			8	9	
Juccess											
Project NPV	(Present Benefits x Probabilit	ty of Su	iccess)	– Prese	ent Cos	ts		£709	,171		
	Activity since Jan 2009 • Draft project plan produ	ced									
	 Design Specification Conspecification 	nplete.	SPEN a	and SSE	E have o	comme	ented c	on			
Project Progress March 09	EDF have been approached with a view to becoming a Tier 1 founding member										
	Draft building functional requirements produced										
	Timescales for completion										
	Construction work to begin March/April 2010 with final completion May 2011										
	Facility – Operation and SP role Overall governance will be carried run by the PNDC Directors, Operational and Research (UoS staff).										
Potential for	The Core Research Programme, will be planned and approved by the PNDC board which comprises of the PNDC directors, UoS finance director and Tier 1 members.										
achieving expected benefits	There are three classes of membership: Founder Tier 1, Tier 1 and Tier 2, each having different voting rights on the PNDC board.										
	For SPEN to get maximum vaplace on the PNDC board to programme to benefit our IF	our ma	aximum	ı advar			_				
	We also anticipate that SPER centre to reduce their time to			-	-	that	will red	uire th	ie use (of the	
Collaborative Partners	Scottish & Southern Energy,	Scottis	h Enter	prise a	nd Uni	versity	of Stra	thclyd	e		
R&D Providers	See Collaborative Partners										

Project Title	IFI 0526 - PD Monitoring of Cables (11 & 33kV)
Description of project	 Partial discharge (PD) monitoring technology is a tool often used for identifying HV cable sections that are at risk of failing in the near future. There are two distinct methods of testing for PD: Long term monitoring to identify the degradation of the cable which signals the increase in risk of failure; and PD mapping which pinpoints the location of any discharge along the route of the cable. Developing the technology to apply these methods gives a network operator the evidence required to assist in targeting investment / cable replacement, with a net improvement in network performance. This project will develop a portable PD monitoring product that can be moved around the network, as tool in the prioritisation in cable replacement.



	Internal	£6,195						ntern	al	£6	5,647	
Expenditure for financial year	External	£21,224		kpenditur FI) financ	•		IS I	Extern	ıal	£4	17,058	
maneral year	Total	£27,419	-	,	ui yee		-	Γotal		£5	£53,705	
Project Cost							ı	ntern	al	£5	5,000	
(Collaborative +	£160	,000		Projected 08/09 costs for SPEN			ı	External		£4	12,650	
external + SPEN)				7 51 211			-	Γotal		£4	£47,650	
Technological area and / or issue addressed by project	 To develor cable section the short minutes the Following those cab undertakethor Based on identified replaced. It is planned to the short cable to the short cable the short cable to the short cabl	 those cable sections, which are registering the highest level of discharge, will be undertaken. Based on the PD maps obtained, any areas of concentrated PD activity, which are identified as critical, will be subject to review and selected cable sections will be replaced. The cable/joints removed will then be tested to validate PD test results. It is planned that the test results will be collated in a database, which, in conjunction with results from the testing carried out by other UK DNOs, will allow for advancements 										
		n the knowledge rules for future PD testing technology. Technological Desired										
Type(s) of	Increme	ntal	S	gnificant				itutio			Radical	
innovation involved	No			Yes			ľ	No			No	
Expected Benefits of Project	to cable of aid justifice Anticipate	ng PD moni degradatior cation and ed key ben nrough targ	n will as prioritis efits wi	sist with ing of cap II be in th	cable pital s ne are	replace pend. a of C	emei ML a	nt dec	ision-r impro	nakir veme	ng. It w	rill also
Expected Timescale to adoption	1-2	2 Years		Duration once as			:		5	S Yea	rs	
Probability of									tart –			
Success	!	50%		1	2	3	4	5	6	7	8	9
Project NPV	Present Bene Costs	fits x Proba	bility o	f Success)	– Pre	sent		1	£1	108,6	61	
Project Progress March 09	Due to the nature of on-line cable PD monitoring, the availability of a suitable earthing connection is necessary. 18 Primary substations were surveyed for suitable connections with only half being appropriate. As part of follow up visits from substation inspections where handheld PD monitors had picked up background PD, more in depth surveys were carried out at Haggs Road, Strathaven and Linlithgow Primaries to ascertain severity of PD.											



	At both Haggs Road and Strathaven there was some PD found in 2 cable circuits and again these will be monitored for an increase.
Potential for achieving expected benefits	Having correctly verified sources of PD in cable and identified cables with PD in the area of concern, the next stage is to monitor the top 20 most problematic circuits in both SPM and SPD. If these cable sections are found to have high levels of PD it is planned to identify location of PD section, expose cable section and replace with healthy cable.
Collaborative Partners	N/A
R&D Providers	HVPD (Formally IPEC HV)

	1								
Project Title	IFI 0532 - AURA-NN	15							
Description of project	This project aims t realise the notion of operator provides t (asset use, etc.).	of an active	distributio	n network and enh	nance the	service a network			
Expenditure for financial year Project Cost	External £1. Total £2.	9,290 81,492 20,782	(IFI) finan	re in previous cial years 08/09 costs for	Internal External Total Internal	£398,313 £15,000			
(Collaborative + external + SPEN)	£5,962,636	•	SPEN		External Total	£176,823 £320,000			
Technological area and / or issue addressed by project	 Distributed Gerof DG to the need of DG to the need of Develop a contal allow distributed The SP portion of the new / existing general Although relevant to the will be to overcomed overcoming cooling and to be described on the provided HTML. 	 of DG to the network; Develop a controller that will monitor electricity networks, isolate faults quickly and allow distributed generation to remain connected and operating. The SP portion of this work is to focus on constraint management techniques for use on new / existing generation connections, focussing on the 33kV and 132kV networks. Although relevant to both SP-D and SP-M networks, the principle focus in case studies will be to overcome existing limitations in SP-M, with a focus on: Overcoming complexity of existing hard-wired intertripping schemes Determining a solution for managing multiple generation connections in a given locality Developing and implementing a system that can work in harmony with existing 							
Type(s) of	Incremental		ficant	Technologica substitution	1	Radical			
innovation involved	No	N	lo	No		Yes			
Expected Benefits of Project	Benefits are expected to include: Development of a constraint management solution with relevant experts Implement solution and prove concept Potential to create Registered Power Zone for additional revenue on the DG incentive Maximisation of the contribution of DG to the electricity network; Reduction in carbon emissions and help towards the UK governments climate change targets; Reduction in network losses by having the source of generation close to the load; Improvement in quality and security of supply; Improvement in network resilience; and								

 $\dot{\rm R}$ Reducing the current market failures to increase network capacity for DG.



Expected Timescale to adoption	7 Years	Duration of benefit once achieved 20 Years									
5 1 1 1111 6		TRL Development (Start – Current)									
Probability of Success	25%	1	2	3	4	5	6	7	8	9	
Success						+					
Project NPV	(Present Benefits x Probability of Success) – Present Costs	£-364,068 The figure is negative as this is a costly project starting from a low TRL									
Project Progress March 09	 AuRA-NMS WP1 (System Design) have currently developed voltage control, thermal ratings and restoration algorithms based on DNO requirements. At this stage of the project individual algorithms are in the process of laboratory testing. Additionally work is underway on the development of suitable arbitration functionality to enable AuRA controllers to implement multiple functions where control instruction might otherwise conflict. AuRA-NMS WP2 (Communications design) has been driven from the outputs of WP1. and is well underway. AuRA-NMS WP3 (Business Case work) is looking the benefits of deployment of the AuRA solution and examining potential impacts on network losses. Further work will be required lifetime costs of solution and specific business cases for the DNO 										
Potential for achieving expected benefits	 AuRA-NMS R&D work is on target to deliver the key requirements of the industrial parties. There is the potential to develop the work further by adding to the scope, at this stage of the project it is accepted that further work of algorithm development and testing will be required prior to deployment of the technology to connect additional DG The integration works requirements have been discussed with ABB and AuRA WP. SP is keen to develop project outputs so that a closed – loop trial may be made possible as functions become refined through testing. 										
Collaborative Partners	EDF-Energy, EPSRC Strategic										
R&D Providers	ABB, Universities: Imperial Co Loughborough, Bath, Manch	_	London	(lead),	Strath	clyde,	Durhar	n, Edin	burgh,		

Project Title	IFI 0535 - Rad	IFI 0535 - Radiometric Arc Fault Location							
Description of project		Applied research, and follow up installation of a system to triangulate fault locations on overhead lines from the high frequency radio wave signatures produced from an arcing fault.							
Expenditure for	Internal External	£12,204	Expenditure in previous (IFI) financial	Internal External	£4,767				
financial year	Total	£21,320 £33,523	years	Total	£53,902 £58,669				
Project Cost (Collaborative +			Projected 09/00 costs	Internal	£7,000				
	£292,000		Projected 08/09 costs for SPEN	External	£37,000				
external + SPEN)			101 31 211	Total	£44,000				
Technological area and / or issue addressed by project	 There is with the If antenr to the GS If a fault base sta 	 The principle of the technology is: There is a correlation between RF discharges and network faults on overhead lines with the RF signal being picked up by a radio antenna up to around 70km away If antennae are spread across the network, a mesh is formed – in a similar manner to the GSM network 							



Type(s) of	Incremental	S	ignifica	int		Techno subst	ologica		Radical		
innovation involved	No		Yes			Ν	lo		No		
Expected Benefits of Project	If successful, the use of radiometric 'cells' could be used to accurately locate fault locations on all overhead line networks within that zone.									fault	
Expected Timescale to adoption	3 Years		Durat achie	tion of ved	benef	it once	•		10 Ye	ears	
Probability of				7	RL De	velopr	nent (Start –	Current	t)	
Success	25% 1 2			2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present Costs £45,787								7		
Project Progress June 09	3 of the 4 monitoring s Shotts – Dec 2008; Kirk online in May 2009 commissioned) • All 3 are collecting • A number of correcollected	intilloc (some	h and E equip mount	Bellshill ment s of rac	Feb 2 proble	2009, w ems ar tric dat	vith De re del ta,	laying	this las	t site	being
Potential for achieving expected benefits	The project has achieved a degree of success already and the analysis of the data collected so far is ongoing. As the project has progressed and more 'in the field' experience has been gathered it has become possible to make changes to the equipment setup which allow the sensitivity of the equipment to be increased and data to be gathered more quickly thus increasing the chances of success.										
Collaborative Partners	Western Power Distribution, Scottish & Southern Energy, Central Networks, Electricity North West, CE Electric UK										
R&D Providers	University of Strathclyo	de									

Project Title	IFI 0540 - MANtIS (M	lanaging Activ	ve Netwo	rks throu	gh Intelligent	Systems)		
Description of project	demonstrate how th	e developme work control	nt and in and prote	tegration ection scl	of key enabl nemes to be i), MANtIS aims to ing technologies will ncorporated and will		
Europalitumo for	Internal £4,	,456	Expendi	iture in	Internal	£6,141		
Expenditure for financial year	External £1,	,899	previou		External	£18,227		
imaneiai yeai	Total £6,	,354	financial years		Total	£24,368		
Project Cost		Projected		Internal	£4,000			
(Collaborative +	£2,453,03	08/09 costs for SPEN		External	£16,500			
external + SPEN)				Total	£20,500			
Technological area and / or issue addressed by project	The project will addre	ess the scenar	ios where	e fault cui	rent is seen as	s a major obstacle to		
Type(s) of	Incremental	Signific	ant		nological stitution	Radical		
innovation involved	Yes	Yes			No	No		
Expected Benefits of Project	• Provision of fault ride-through canabilities by control of fault current limiting l							



	realised. The ability to accommodat network reinforcement.	e greater penetration of DG without the need for costly				
Expected Timescale to adoption	3 Years	Duration of benefit once achieved 10 Years				
Dechability of		TRL Development (Start – Current) A range of project TRL will apply				
Probability of Success 50%	1 2 3 4 5 6 7 8 9					
Project NPV	(Present Benefits x Probability of Success) – Present Costs has been aligned to a specific network application.					
Project Progress March 09	SPEN provided project partner projects. Project suspended in Q1 of 200	s with a summary of learning points from other similar				
Potential for achieving expected benefits	The project has been suspended indefinitely.					
Collaborative Partners	Rolls-Royce, Manchester and Strathclyde University, TSB (via Technology Programme)					
R&D Providers	Rolls-Royce, Manchester and St	rathclyde University				

Project Title	IFI 0607 - LV N	IFI 0607 - LV Network Automation							
Description of project	Scottish Powe implementing consist of one It is two ma communication will be the F	The aim of a Low Voltage Automation (LVA) project is to provide a trial system on Scottish Power Energy Networks (SPEN's) LV network, which will prove the benefits of implementing a larger scale LVA system across the LV networks. The trial system will consist of one LVA CCU (modified old CCU) and one phase LVA switch. It is two major parts that will be validated in the project. The first one is the communication from the control point to the LVA switch. The communication technique will be the Power Line Communication (PLC). The second part is the mechanical behaviour and the control of the Magnetic vacuum Switch from EPS.							
	Internal £33,954		Internal	£12,830					
Expenditure for financial year	External	£67,374	Expenditure in previous (IFI) financial years	External	£33,964				
,	Total	£101,327		Total	£46,794				
Project Cost				Internal	£15,000				
(Collaborative +	£257,	,775	Projected 08/09 costs for SPEN	External	£70,000				
external + SPEN)				Total	£115,000				
Technological area and / or issue addressed by project	The Low Voltage networks contribute ~11% CI and ~15.5% CML between the SP-D / SP-M networks (taken from 2003/04 NaFIRs report). Both proposals aim to produce, install and test prototype systems on a trial network, providing a proof of concept and evaluating performance of the installation on the LV distribution network. Application will be to focus on high customer density, worst performing LV circuits.								



Type(s) of	Incremental	S	ignifica	ant			ologica itution	I	Radical		
innovation involved	No	Yes				No			No		
Expected Benefits of Project	 Reduction of CM Increased asset I stresses during fa Reduced cost and location 	 stresses during fault location Reduced cost and time of fault location through rapid identification of faults location 									
Expected Timescale to adoption	3 Years		Duration of benefit once achieved						10 Ye	ars	
					ΓRL De	velopr	nent (S	tart – C	Current)	
Probability of Success	50%		1	2	3	4	5	6	7	8	9
Success											
Project NPV	oject NPV (Present Benefits x Probability of Success) – Present Costs £526,7k										
Project Progress March 09	 The overall plan is spl "Mechanical step" "PLC trial step" "LVA prototype s The "Mechanical simplementation man the LVA prototype ha 	o" tep" step" i ufacture	s the e and v	phas verificat	e tha ion. It	is finis	hed wh	nen the	mecha	anical p	art of
Potential for achieving expected benefits	the LVA prototype has been verified and demonstrated from mechanical point of view. The "PLC trial step" will end up with the first PLC validation on SPEN site. The purpose of this phase is to validate if PLC communication protocol seems to work on the SPEN LV network. Minimal new electronic HW and SW will be developed to perform this validation. At this state there will not be a switch at all, just a validation of the PLC data quality. To test the PLC communication and which chip is best suited a communication test will be made using development kits from the suppliers. Two test scenarios, one with PLC-communication between two PC's and one manoeuvring a switch simulator connected to a FastNet from a PC via PLC. This project is on target.										
Collaborative Partners	None										
R&D Providers	RADIUS								•	•	

Project Title	IFI 0615 - ScottishPower Advanced Research Centre (SPARC)
Description of project	 Asset Engineering: Field based activities, concentrating on the technologies used to gather and interpret data then control and manage individual assets. Asset Strategy: Office, desktop, PC based analytical activities including the analysis of data, concentrating on underlying trends of asset populations (from asset ageing to network performance). System Development: Forward looking network design activities considering the connectivity between the assets. It should consider both the medium term (5 years) and longer-term trends (>10 years), which will affect the design of the



	network (e.g. load,	, genera	ition, st	andar	ds, re	gulati	ions, C	Ofgem	incen	itives/	'penal	ties).
Expenditure for financial year	A number of related processing for the second secon	4 008	Exper	levelo nditure inanci	e in pı	reviou		Inter Exte	rnal rnal	£	4,371 17,08	3
Project Cost (Collaborative + external + SPEN)	£460,083 Project SPEN			cted 0	8/09	costs	for	Internal External Total		£	£21,454 £6,000 £150,000 £156,000	
Technological area and / or issue addressed by project	 enable better use of Asset Strategy resident of position System Development 	 enable better use of individual assets. Asset Strategy research stream focuses on methods and tools that enable between the management of populations of assets. 						etter				
Type(s) of innovation involved	Incremental Significar			nt			nologi stitutio			Ra	dical	
	Yes		Yes				Yes			l	No	
Expected Benefits of Project	Research activities will seek to realise business benefits across a range of areas including system performance, OPEX and CAPEX. Key areas have been identified in the SPARC proposal, which are being used to form the basis of a more comprehensive programme of deliverable projects.											
Expected Timescale to adoption	3 Years				achi					10 Yea		
Probability of Success	Varies per pro	oject		1	TR 2	L Dev	elopm 4	ent (S	Start – 6	- Curre	ent) 8	9
Project NPV	(Present Benefits x Prol Success) – Present Cost		of	TBC In development for the core projects in each workstream								
Project Progress March 09	An outline of progress made on the three existing SPARC themes of Investment Strategy, System Development and Asset Technology, complete with deliverables, is provided below: 'Investment Strategy' Theme •PEDA - Enhanced the existing diagnostic system for online implementation and operation of telemetry processor; improved user interface for ease of use; identified requirement for protection settings database to underpin automated analysis of fault records; fault record analysis system design and development ongoing (A meeting SPEN and Iberdrola, in July 09, discussed a possible change in scope of the PEDA PhD project). Following departure of Gary Napier a new PhD student will be appointed to resume this work in September '09. •Network Control Point Alarm Processor The telemetry processor was adapted for the processing of Network Control Point alarms (conducted in association with John Kirkwood of SPEN). A prototype was demonstrated to SPEN in August '08. Further SPEN input is required to define additional rules and any potential for additional functionality. 'System Development' Theme •Distributed Generation Penetration Study — A report was produced on the estimated growth of different types of distributed generation (at EHV, HV and micro) from a						es, is and tified fault SPEN oject). e this Point was tional					



baseline in 2010 to 2015 on an annual basis, based on Supergen Future Networks Scenarios. This approach was presented (i.e. presentation entitled "An Approach to Estimating DG Penetration") at SPEN's Stakeholder Price Control Workshop in August 2008.

Optimal Distribution Network Architectures

Development of network design criteria and methodologies to maximise DG contribution and permit resolution of conflicts between maximisation of DG output, maximisation of reliability and minimisation of network losses while respecting fault level constraints A literature review was conducted and heuristic methods of loss minimisation and network optimisation were investigated. Initial testing of an algorithm on rudimentary network design was conducted. A one month placement has been arranged for August 2009 where the PhD student will develop a complex 11kV network model forming the basis for future algorithm development and testing, while also gaining an appreciation of the user requirements of the network optimisation algorithm developed for network design, planning and operation.

'Asset Technology' Theme

•PD Diagnostics in MV Cables – A literature review was conducted. A high frequency model of the CT was developed and the subsequent effect of PD signal on CT core material analysed using the developed model. A Remote Partial Discharge Mapping Unit (RPDMS) was developed (i.e. developed filter program, PD database and GUI for client and server) and laboratory tested. A preliminary substation visit was subsequently carried out in July to assess the feasibility of acquiring PD signals from the transformer earth strap. Frequency Response Analysis of the CT is currently in progress. Three conference publications have been produced and the PhD student is currently working on a journal publication describing this research. Installation of RPDMS in a designated substation is scheduled to take place in August 2009.

- The Investment Strategy theme has undergone a change in personnel, which has
 resulted in the postponement of a progress review meeting, although project
 meetings with SPEN staff involved with this project (i.e. Tom Cumming and Iain
 Watts) have been ongoing.
- The System Development theme has undergone one progress review meeting, held on 2nd June '09 with Diyar Kadar, Colin Bayfield and Carl Woodman of SPEN present.
- The Asset Technology theme has undergone two progress review meetings; the first held on 13th Nov '08 with Paul Cunningham and Jamie McWilliam of SPEN present; and the second held on14th May '09 with Diyar Kadar and Jamie McWilliam of SPEN present.

Potential for achieving expected benefits

- The research programmes are currently progressing in accordance with the original project plans. There has been a change n PhD personnel associated with the PEDA work in the Investment Strategy theme. In addition, following recent discussions with SPEN and Iberdrola, it is possible that the scope of this work may change from that originally defined. A meeting scheduled for early August will confirm and detail this change in scope. It is anticipated that any change in scope requested by SPEN will remain aligned with the deliverables and timescales originally defined.
- Each of the research themes have already offered tangible deliverables, offering
 assurance to stakeholders that the potential for achieving expected benefits is
 being realised within the original timescales defined for each of the three PhD
 projects currently ongoing.
- Discussions are in progress concerning the utilisation of SPARC to support the limited research resource that currently exists within SPEN, such that more short to medium term and timely research deliverables may be achieved (out with the existing PhD arrangements). This may require additional funding.
- Active and regular engagement between SPARC programme managers from both the University of Strathclyde and SP Energy Networks will continue to ensure the successful transition of research outcomes into the business.

Collaborative Partners

N/A



R&D Providers	University of Strathclyde
---------------	---------------------------

Project Title	IFI 0618 - Supergen 1 – FlexNet							
Description of project	FlexNet is a four-year EPSRC funded programme that takes forward the process of preparing electricity networks for a low carbon future and builds on an initial programme of works, FutureNet that is nearing completion. The programme recognises the interdependence of many factors in achieving change through its integration of the work of internationally recognised researchers from disciplines such as social psychology, economics, power systems analysis, power systems technology and public policy and the long-term, radical nature of the changes needed and is not dependant on any particular form of generation							
	Internal £2,864			Internal	£3,324			
Expenditure for financial year	External £41,37	4 Expenditu	re in previous cial vears	External	£2,753			
	Total £44,23			Total	£6,077			
Project Cost				Internal	£5,000			
(Collaborative +	£7.6m	Projected SPEN	Projected 08/09 costs for		£20,000			
external + SPEN)		3.2.4		Total	£25,000			
Technological area and / or issue addressed by project	starting to showcase these so that they can be taken up by the commercial Government and Regulators for practical implementation. Some of the key issues to be addressed by the programme include: How can we judge the degree of flexibility needed? How can flexibility be achieved? How much flexibility should come from primary plant giving margin and ho from secondary plant giving enhanced controllability? What constrains or encourages flexibility, what technologies are accepta what economic frameworks and public policies provide flexibility at the leasilong-term cost?							
Type(s) of	Incremental	Significant	Technolog substituti		Radical			
innovation involved	No	No	No		Yes			
Expected Benefits of Project	 Understanding of flexible network requirements able to cost-effectively deal with a wide range of possible futures Develop networks that can 'think' for themselves Engagement with stakeholders in progressing the research ideas toward deployment Research that forms the basis of policy advice Inputs to the UK government's Energy Review, the UKERC assessment of Intermittency, evidence to select committees of parliament and submissions to OFGEM consultations. 							



Expected Timescale to adoption	3 Years	Duration of benefit once achieved	I Ju years							
		TRL Developmen	nt (Start – Cur	rent)						
Probability of Success	25%	1 2 3 4	5 6	7 8	9					
Success										
	(Present Benefits x	Not calculate	d at this poin	t -	I					
Project NPV	Probability of Success) – Present Costs	■	dependent on flexible network solutions arising from the programme							
Project Progress March 09	The Management Executive meets quarterly and receives detailed progress reports. Thirty PhD projects and 20 research assistants have started although slow recruitment means detailed plans have been adjusted in some cases. Good progress has been made on various forms of modelling: energy resource models, transmission system models and distribution planning models. On top of these there are now outputs to support transmission access review and the security and quality of supply standards. Generic approaches to distribution planning for high DG penetration are being advanced and new technologies such as soft normally-open points are being evaluated. Work on demand-side control has reviewed European experience and proposed operational and settlement options for the UK. Researchers on the Future Energy Mix workstream supported the LENS report with techno-economic appraisals and that work is now disseminated.									
Potential for achieving expected benefits	The new researchers are now integrated in the consortium and working well. Industrial partners have been providing case studies and data to allow researchers to make specific assessments of technologies. The "validation and showcase" workstream is now producing detailed plans for its crucial role in promoting the benefits. Research topics within FlexNet have been identified as directly supportive of the ENSG 2020 Vision and efforts are underway to create some focused studies on this vision. Similarly, we expect benefits for future distribution network design based analysis of the evolution of demand in the electricity sector and demand side management.									
Collaborative Partners		ctish and Southern Energy, Centergy Networks, CE Electric UK,								
R&D Providers	Universities of Bath, Bi Strathclyde and Imperial Co	mingham, Cambridge, Cardi llege London.	ff, Edinburgl	h, Manch	ester,					
Project Title	IFI 0619 - Advanced Cable	echnologies								
Description of project	Advanced Cabling Technologies Programme wrapper for a discrete programme of related IFI cabling projects with a de minimus expenditure level of £40k per annum. A example project being developed under this programme is a concept to reduce excavation and reinstatement costs and improve reliability of 11kV and 33kV jointing systems.									
Expenditure for	Internal £10,196 External £12,219	Expenditure in previous	Internal External	£3,17! £2,902						
financial year	Total £22,415	(IFI) financial years	Total	£6,07						
Project Cost		Projected 09/10 costs for	Internal	£0						
(Collaborative +	c£30,000	SPEN SPEN	External	£0						
external + SPEN)	Total £0									
Technological area and / or issue addressed by project	 The programme addresses cabling technologies and associated issues. The example project considers the following. Given the extensive annual cable jointing activity this project seeks to realise savings on ever-increasing excavation and reinstatement costs as well as improving the reliability of cable joints. 									



	• Enhanced reliability will be achieved by designing out failure mechanisms and reducing the prospect of installation error.											
Type(s) of	Incremental	Sign	ificant		Technological substitution				Radical			
innovation involved	No	No				Yes			No			
Expected Benefits of Project	 Enhanced reliabil error Smaller cable join 	error										
Expected Timescale to adoption	2 Years		Duration of benefit once achieved						3 Years			
	Projects with vari	ious		7	ΓRL De	velopm	nent (S	tart –	Curren	t)		
Probability of Success	Projects with various probabilities of success will be		1	2	3	4	5	6	7	8	9	
	considered								-			
Project NPV	(Present Benefits x Pro	obability o	of Succe	ess) –	Presen	t Costs	,		£90,7	26		
Project Progress March 09	Improved 11kV cable joint project has gone through test stage and is now ready for trials, the 33kV cable joint should be ready at the end of September.											
Potential for achieving expected benefits	This project is on target											
Collaborative Partners	N/A											
R&D Providers	Bound under confiden	ntiality										

Project Title	IFI 0620 - Tower Fo	oundation Rada	r				
Description of project	When tower line circuits have been identified for refurbishment or replacement it is necessary to make an assessment of the foundation condition. Traditional methods involve invasive excavation to expose the foundation blocks for visual inspection. This project will trial underground structure survey technologies already utilised in the civil and geotechnical engineering industries to assess the condition of tower foundations and compare with the findings of traditional techniques.						
- III (Internal	£3,891	Expend	iture in	Internal	£2,000	
Expenditure for financial year	External	E8,178	previou	s (IFI)	External	£1,144	
açıa. yea.	Total	£12,069	financial years		Total	£3,144	
Project Cost	eject Cost Projected		ed	Internal	£0		
(Collaborative +	£51,4	09/10 costs for SPEN		External	£0		
external + SPEN)				Total	£0		
Technological area and / or issue addressed by project	Due to the intensive labour and time effort involved it is normal practice wh excavating foundations to perform an assessment on a 10% sample of towers. T objective with this non - invasive technology is to enable all tower foundations to examined.					nple of towers. The	
Type(s) of	Incremental	mental Significan			nological stitution	Radical	
innovation involved	No	No			Yes	No	



Expected Benefits of Project	Survey times are dramatProven portable equipm environmental damage	 Survey times are dramatically reduced and cheaper Proven portable equipment, allowing easier access to sites with reduced environmental damage 								
Expected Timescale to Adoption	1 Years	Durat achie		benefi	t once			10 Ye	ars	
				TRL De	velopn	nent (S	Start – C	Current	:)	
Probability of Success	75%	1	2	3	4	5	6	7	8	9
Success									>	
Project NPV	(Present Benefits x Probabili Costs	ty of Su	ıccess)	– Pres	ent			£14,2	20	
Project Progress March 09	Transient Dynamic F and/ or length of bu Linear Polarisation - corrosion of steel co Ground Penetrating Ultrasound - determ Ultrasonic - provide In order to assess the merits findings of the radar survey withe results of the two technic Upon completion of the projeusing the radar technique an out.	 <u>Ultrasound</u> – determines the quality of concrete under test <u>Ultrasonic</u> – provides indication of steel integrity In order to assess the merits of this technology, several sampled digs based on the findings of the radar survey were carried out in order to provide a comparison between the results of the two techniques. Upon completion of the project, 35 out of the 37 towers on the 'D Route' were surveyed using the radar technique and two were selected to have digging assessments carried 								
Potential for achieving expected benefits	Due to the large amounts of data obtained from the radar survey, the speed at which it can be gathered and the non-difficulty in gaining wayleave access, it is considered that this technology could be of use in sampling long tower routes if a general condition assessment is required. It is strongly advised however, that if decisions such as whether to build upon existing foundations are to be clarified, that several sampled digs are used to backup the information obtained from a radar survey, due to its limitations. This project is now closed.									
Collaborative Partners	None									
R&D Providers	Sterling Geophysical Surveys	Ltd								

Project Title	IFI 0621 – Energy Innovation Centre
Description of project	The CEIC will be a unique new facility designed to enable start-up companies and individuals to turn innovative ideas into commercially successful products and services for our industry. It will be a market driven organisation strategically positioned to address the critical stages of the innovation cycle between proof of concept and early production stage. By focussing on these essential stages, the CEIC is the key link between the academic type R&D we fund and the specific needs we have for innovation in the form of tangible products and services at the network operational level.



	Internal £2,	864	Evnond	iture in	Internal		£0			
Expenditure for financial year	External £1,	374	previo	us (IFI)	External		£0			
iniancial year	Total £4,	238	financia	al years	Total		£0			
Total Duoingt Conta			Dunia		Internal		£5,0	000		
Total Project Costs (Collaborative +	£500k		09/10 c	ected osts for	External			0,000		
external + SPEN)			SP	EN	Total		£15	5,000		
Technological area and / or issue addressed by project	with Universities for services. This project businesses and indiperformance of the money to accelerate 3 other DNOs and hat addition further Equipame businesses to phave been considered Power. As the centred	the Energy Innovation Centre is a new concept for DNOs. Traditionally, DNOs work ith Universities for R&D and established suppliers for new innovative products and exvices. This project actively accesses a new mainly untapped market of small usinesses and individuals to provide innovative solutions which will improve the erformance of the network. The purpose of the centre is to support businesses via IF oney to accelerate new technologies to market. This approach is in collaboration with other DNOs and has attracted an £2.1 million of public investment into the sector. In Edition further Equity Investment is being attracted into the sector to support these time businesses to progress from TRL8 to full commercialisation. To date 12 businesses have been considered for IFI investment with 3 receiving investment from Scottish ower. As the centre develops over the next 6 months the number of opportunities for exottish Power to invest through this mechanism will increase.								
Type(s) of innovation involved	Incremental Tech Transfer Significant	Project Be Ratin		Project	Residual F	Risk		all Proj Score	ect	
	Radical	Per pro	ject		Per project					
Expected Benefits of Project	 Increased exposi Reduction in risk Increased collabo Leveraging addit Improved perfor 	and cost of morative working onal investme	anaging p g betwee ent into tl	orojects n DNOs. ne sector		blic an	nd priva	te moi	ney.	
Expected Timescale to adoption	1-2 years dependir project	g on Du	ration of achi		nce	1	10-20 y	ears		
			TF	RL Develo	pment (St	art – C	Current)		ı	
Probability of Success	75%	1	2	3 4	5	6	7	8	9	
Project NPV		NPV is calcula	ted on an	individua	al project	basis				
Potential for achieving expected benefits	The majority of KPI's are being achieved by the centre which supports that the benefit to the DNOs will be achieved.								enefits	
Project Progress 09	of effort has gone in centre and the centre. To date the centre investment in 6. This	This is the first year of the Energy Innovation Centre's operation. During this time a lot of effort has gone into developing a collaborative approach across the DNOs and the centre and the centre developing its networks and operational framework. To date the centre has 40 leads, DNOs have considered 12 businesses and achieved investment in 6. This is set to increase as the centre launches its marketing strategy to attract ideas and market potential technology gaps identified by the DNOs.								
Collaborative Partners	Electricity North W	lectricity North West, Scottish & Southern Energy, CE Electric, North West evelopment Agency, EATL								
R&D Provider	Various									



Project Title	IFI 0624 - Impact of Climate Change, Energy (Phase 2) - MET Office								
		_			-	a year long research acilitated by the Met			
Description of	Climate change and the impact on our environment is a major issue facing the today. The latest findings from latest research confirm that global mean temper continues to rise and 'almost certainly' attributable to man's activities in burnin fuels. Regional changes in temperature and precipitation patterns, wind and activity, and floods and storms have the potential to profoundly affect society.								
Description of project	scenarios to energy participating compan	The project aims to provide practical guidance on the application of climate change scenarios to energy industry processes. It will look to make recommendations to the participating companies on how best to asses the impacts of climate change on the planning and operation of the supply industry.							
	standards. How will the rating of lines, ca	It will investigate the need for transmission and distribution systems to adopt new standards. How will climate change affect the risk of infrastructure damage; and, will the rating of lines, cables and transformers be affected? The networks' proportion of the project was funded through the Innovation Funding Incentive, as is covered in this summary report.							
Expenditure for	Internal £5,0		Interna	•					
financial year	External £1,7		Expenditure (IFI) financia		Externa	•			
	Total £6,7	/87			Total Interna	£50,674			
Project Cost (Collaborative +	£450 000	£450,000 Projected 09/10 costs for SPEN				l £0 al £0			
external + SPEN)	1430,000					£ 0			
Technological area and / or issue addressed by project	 the network built Create methodo models (dealing v Assess the important process 	f the net obal climation impact of potential today is logy for with limit tance of ifference	work assets in the are expect on the operation impact of clifit for purpose prediction of cations in spation temporal reso	nstalled in 200 ced to occur or	5-2010 ver this to the elector networe. tricity deal resolution generated the colonical culturation of	vill still be in place in cimeframe, which are ctricity network. ork assets will ensure emand using climate			
Type(s) of	Incremental	Sig	gnificant	Technolog substitut	-	Radical			
innovation involved	Yes		Yes	No		No			
Expected Benefits of Project	 The expected benefits of project are: Probabilistic understanding of likely future electricity and gas demand Model for projecting meteorologically driven demand suitable for inclusion in climate model or for application to climate model output Demand from 'Energy' climate model simulation Reporting of the affect of temporal and spatial resolution on the demand calculation, and recommendations for projecting demand from UKCIP08 when available Recommendations for improvements in demand modelling approach if necessary. Investment decisions for energy networks – expected impacts of climate change, such as land surface modelling and urban heat island effects on network assets can be taken into account when making future investments. 								



		1									
Expected Timescale to adoption	1 Year		ition o achie	f bene ved	fit		5	50 Yea	rs		
			Т	RL Dev	elopn	nent (S	Start –	- Current)			
Probability of	75%	1	2	3	4	5	6	7	8	9	
Success											
Project NPV	(Present Benefits x Probability of Costs	Present Benefits x Probability of Success) – Present osts Not Calculated									
Project Progress March 09	 Developed innovative new applications so that the industion investigated future wind recontinued uncertainty of fut investment decisions. Modelled future soil condition understand the cost and be network. Built a tool to enable UK coassess if sea level rise should Investigated how the urban Networks can develop plans. Produced guidance to help in change such as the United K climate change (UKCIPO8). UKCIPO8 will enhance region. Delivered new site-specific radiation that account for clinclimate expectations. Examined the relationship is performance with a view to continue the sexion of the project has found that because. With a few exceptions, such there is currently no evidence example existing design state change. The risk profile for transform will be exceeded more often. Soil conditions will change; moisture are expected. Future by increasing average summed. Soil conditions will change; moisture are expected. Future by increasing average summed. The output of thermal power considered, especially during planned. Historical climatologies are in new climatologies that take and will improve demand for wind resource is uncertain significant challenge. Althout highlighted possible strategic. 	stry is be resource ture with cenefits coastal and the competition of	d their of instant of	placed rabling wer. The rimpa stalling marine ed in media ed in me	to ad the his winct on cable sites hore do may ure in ublic do pacts available to predict the predict of the pr	lapt to indust II assist cables es for of interestall. chang cities. lomain Prograture, sions of equipment of	climate try to strick a so that a more erest to ge in the can be erns a cure net cuipment wind can be erns a cure net cuipments in contact of the can be end	te char under under manager at Commerce residue of being speed and new state of the cities. In the cities of the c	restand gemen in panie lient for creen on cli scenario con cli scenario con cli scenario con real twork resilier in apparanta in con con con con con con con con con co	If the t and as can uture ed to that smale ios of solar alistic fault ince. Tratus, s. For quire ature ature in soil udies nately earlier in the cation of the cation of the cation of the cation in the cation into a solar into	



Potential for achieving expected benefits	In order for the momentum of this project to be retained an energy and climate change industry group will be set up. This group will continue to share the latest science and its application to business. This would meet as necessary to discuss latest innovations and developments in climate science with leading experts. The group would share thoughts and ideas on areas of common interest as Companies work to adapt to climate change.
Collaborative Partners	Networks Only: C.E. Electric, National Grid, Electricity North West, Western Power Distribution Networks, Generation & Supply: E.ON, EDF Energy, Northern Ireland Electricity, Scottish & Southern Energy, ScottishPower Generation & Supply Only: Centrica, RWE, npower
R&D Providers	Met Office

Project Title	IFI 0625 - Vegetation	Manage	ement - ADAS						
	maintenance require commitment to this growth rates would	regetation management in the vicinity of overhead lines represents a significant naintenance requirement and associated budget spend. While there is an on-going ommitment to this issue, it is recognised that a better understanding of vegetation rowth rates would greatly assist in vegetation management strategies and decision naking; helping direct the focus of activity.							
Description of project	between key environ and vegetation grow	ne project will seek to develop a software model that will analyse the relationships etween key environmental variables (including the potential impact of climate change) and vegetation growth rate, for different vegetation types. The model will be used to ensider the costs and benefits of undertaking vegetation management to different specifications.							
	of growth data, wh	bllowing tree cutting at selected sites the model will be validated against the first year growth data, which will be determined by laser measurement. The model will be be optimised based on annual growth rates determined over a further ree-year period.							
	Internal £4,25	50			Internal	£3,171			
Expenditure for financial year	External £100	,374	Expenditure in previous (IFI) financial years		Externa	f £132,758			
iniancial year	Total £104	,624	(ii i) illiancial	i) illialiciai years		£135,929			
Project Cost					Internal	£8,000			
(Collaborative +	£1,744,000		Projected 09 SPEN	/10 costs for	Externa	£41,000			
external + SPEN)			31 214		Total	£49,000			
Technological area and / or issue addressed by project	 "bio-climatic" zor It will involve cu common specific The output is exp cycles. 	 "bio-climatic" zones that are found across the country. It will involve cuts made to 2000 sample areas across the identified zones to a common specification, followed by monitoring to confirm growth. The output is expected to lead to modelling software that can portray different cut cycles. The common UK project should provide further evidence / justification in future 							
Type(s) of	Incremental	Się	gnificant	Technolo substitut	_	Radical			
innovation involved	No		Yes	No		No			
Expected Benefits of Project	 The model developed will identify areas that will require more frequent tree cutting to maintain safe clearance distances and meet legal requirements. Evidence-based decisions on the frequency and location of tree cutting will enhance network resilience and therefore improve security of supply and associated regulatory performance (CI and CML savings). Improved targeting of OPEX may be realised through proactive cutting and 								



	extending the cutting cycle ir	high a	nd lov	v grow	th are	eas res	pectiv	ely.		
Expected Timescale to adoption	2 Years Duration of benefit once achieved 20 Years									
5 1 1 1111			TF	RL Dev	elopn	nent (S	tart –	Currer	nt)	
Probability of Success	75%	1	2	3	4	5	6	7	8	9
3466633										
Project NPV	(Present Benefits x Probability of Costs	Present Benefits x Probability of Success) – Present £681.3k								
Project Progress March 09	All sites in SPM and SPD have bee	en cut	and m	easure	ed wit	h resul	lts beii	ng pas	sed ba	ick to
Potential for achieving expected benefits	providing some significant insigh	DAS are now processing the results from the first years monitoring in detail. This is roviding some significant insights into growth rates across the bioclimatic zones and be potential impacts of climate change.								
Collaborative Partners	lectricity North West, Scottish and Southern Energy, Central Networks and National rid.									
R&D Providers	ADAS									

Project Title	IFI 0628 - Asset	Decision Supp	ort Dashboard				
Description of project	centralised dec are bringing to data fusion) in informed short, The desire to m will identify op	isions around of pether information a single control in medium and langue from an 'in portunities for sapplied in other sapplied in other pethods.	ors of high value assets compliance, asset availabilitication from disparate source omposite picture of the errong-term decisions on their investigative' use of data town better use of asset data by ther markets with the deve	y, performance es and platfor ovironment in asset base. vards a 'predic' considering to	e and cost. They ims (concept of order to make tive' use of data pols, techniques		
Expenditure for	Internal	£7,170	Expenditure in previous	Internal	£6,392		
financial year	External	£47,652	(IFI) financial years	External	£42,092		
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Total	£54,822	()	Total	£48,484		
Project Cost			Due is stad 00/00 seets for	Internal	£15000		
(Collaborative +	£98,3	391	Projected 08/09 costs for SPEN	External	£80000		
external + SPEN)			31 E14	Total	£95000		
Technological area and / or issue addressed by project	 The use of potentially untapped high value data that could be utilised for 'predictive' decision-making. A three-phase programme has been identified to fully address SPEN's requirements. Phase 1 proves the concept with ScottishPower's existing Asset Inspection System (AIS) database. Prior to considering subsequent phases a project closeout review will be undertaken to ensure that outcomes meet business needs and make recommendations as to the best way forward. Phase 2 applies to further AIS information and other databases to provide asset performance history and trending. Phase 3 includes the addition of SCADA outputs to produce a health-monitoring dashboard of alerts. Future diagnostics and prognostic systems as a learning system would also be considered. 						



Type(s) of	Incremental	S	ign	ificant			echnolo ubstitu	_		Radic	al
innovation involved	Yes		No				No				
Expected Benefits of Project	information extracted fro	e main business benefit will be to enable better asset decision-making based on ke formation extracted from AIS and displayed and trended, by traffic light status, in ototype Asset Decision Support Dashboard web-enabled risk portal.								-	
Expected Timescale to adoption	1 Year	1 Year Duration of benefit once achieved							10 Ye		
5 1 1 111 C			TRL Developmen					tart – C	urrent)	
Probability of Success	50%	1		2	3	4	5	6	7	8	9
									\geq		
Project NPV	(Present Benefits x Proba Costs	bility o	f Su	iccess)	– Pres	ent		163,23 hases k			
Project Progress March 09	 Project complete and Asset Decision Supp Investment Strategy 	ort Da		oard (develo	oed by	DS&S	and p	resent	ed to	SPEN
Potential for achieving expected benefits	Progress to phase 2 to be	rogress to phase 2 to be discussed in Q3 of 2009.									
Collaborative Partners	N/A										
R&D Providers	Data Systems & Solutions	Data Systems & Solutions (DS&S)									

Project Title	IFI 0701 - ENA IFI	Projects			
Description of project			under development with ork Operators through the		-
	Internal	£2,864	Expenditure in	Internal	£7,560
Expenditure for financial year	External	£3,842	previous (IFI) financial	External	£6,554
inianciai yeai	Total	£6,706	years	Total	£14,114
Project Cost			- 1 - 1 - 2 - 1 - 2 - 1	Internal	£1,500
(Collaborative +	c£30,	000	Projected 08/09 costs for SPEN	External	£2,000
external + SPEN)			10. 5. 2.1	Total	£3,500
Technological area and / or issue addressed by project	been identified be investigation and SG14 Earthing voltage earth resistance of Cable Harmon of cable and models approached the project and other items of the composition of the project and	y the ENA Worldevelopment. Ing Project — Description substitution substitution substitution substitution substitution substitution substitution description description description of equipment and literature of equipment and stability out testing and of the stability of the stability of a matrix	evelop new techniques to higher voltage 'hot extraor evelop new techniques to higher voltage 'hot extraor earth systems. Modelling - The report of components. Particularibution networks, as this in modelling of cables is runn a range of LoM relay lity of these relays where dat a range of relay settings ar	and which reconstruction assess the incovers the determinant as widespreads in order to a confronted tings. This info	mpact of lower or measure the railed modelling is paid to cable tial objective of read as that for develop a clear by a range of ormation will be



Type(s) of	Incremental	S	ignifica	int		Techno substit	_		1	Radical	
innovation involved	Yes		Yes			N	0			No	
Expected Benefits of Project	on HV systems. effective, safe of between HV and costly to achieve Cable Harmonic an ETR type guide modelling require LoM - An improversulting in a redisturbances. Moreoverseless and the same of th	SG14 Earthing Project — This project will investigate the effects of LV earth systems on HV systems. The results of this should determine the means to provide cost effective, safe earthing system without the need for expensive separations between HV and LV electrodes which in a PME system may be impractical and costly to achieve and maintain. Cable Harmonic Impedance Modelling - The study objective is the development of an ETR type guidance note to supplement G5/4 (2001) and help reduce and simplify modelling requirements for relatively small capacity 33kV and 11kV connections LoM - An improved understanding of LoM relays. Use of more effective settings resulting in a reduced number of unwanted generator trips due to system disturbances. More effective use of LoM relays (e.g. as interface protection resulting in reduced installation costs								e cost rations al and ent of mplify ns ettings ystem	
Expected Timescale to adoption	1 - 10 Years	1 - 10 Years Duration of benefit once achieved 10 – 40 Years									
Probability of						velopn	1	tart – C	1	t)	
Success	25 - 75%		1	2	3	4	5	6	7	8	9
_									<u> </u>		
Project NPV	(Present Benefits x Probability of Success Present Costs	Probability of Success) – Note – Project costs include implementation and have been calculated by the ENA assuming a typical									
Project Progress March 09	SG14 Earthing Project 2008) the project teal analysis at two live supotentials created by completely new and equipment when the to quite closely mais substations but they installations in terms. Cable Harmonic Imp the first section of wimodelling issues on tit is called is the focavailable until the mean LoM - The final reports.	m were ubstation a close help to re is an tch the were exported on the original cuts of the treatment of the treatment of the original cuts of the treatment of	able to ns) tha to expla HV ear theor ach con earthin Mode the con he final f the w	confirt the LN lectrica in why th faultetical insiderang requilling - able moject brill reportable in lectrical in lectric	m by of elect lly sep there to necessary or electron end modelling ief. The ort who group did and	calculaterode syparated is so I quipme neasure e componts. erim reg which e extendich is to on the will be	ion and steem in HV institute entire quite entire e	d meas nteract stallation vidence e close alts at I that the mas been esses to the bull the time uly 200 nted as	urements with on. The of do by. It the the vastern issues the teorief to the and the cone and th	ent (inc n the ex e findin amage was po two livi st majo ued foll chnical o stage d will r	luding sternal gs are to LV ossible e test rity of cable 2.5 as not be chnical
Potential for achieving expected benefits	SG14 Earthing Project - High. The results from tests and simulations can be used to propose a recommended procedure for measuring transfer potential between HV and LV systems, suitable for inclusion in a DNO policy document. Cable Harmonic Impedance Modelling - The frequency dependent behaviour of overhead lines and cables was assessed. A sensitivity analysis has shown that simplified models and power frequency models may be used to represent the harmonic behaviour of a single core conductor overhead line and cable with a reasonable degree of accuracy over the frequency range assessed. LOM - The final report provides the basis for new settings guidelines which should enable the majority of perceived benefits to be achieved.										
Collaborative Partners	UK Distribution Network Operators (DNOs)										
R&D Providers	SG17 Lightning Prote SG14 Earthing Projec					:					



Project Title	IFI 0702 - Lat	tice Steel To	ower Pr	otectiv	e Coa	tings	!					
Description of project	The develop towers to re developed a without the risk of becor sensitised it i	The development of a prototype single coat epoxy protective coating for lattice steel owers to replace the two coat alkyd paint currently in use. In 2000 ScottishPower eveloped and introduced a single coat epoxy coating for lattice towers. However, without the use of appropriate protective clothing and barrier creams there was a small isk of becoming sensitised to the irritants in the paint. Once the applicator becomes ensitised it is unlikely that they will be able to tolerate using epoxy paints in the future. In conjunction with the Epoxy paint manufacturer this project will explore the removal								Power wever, a small comes future.		
	coating. One	irritants in the paint system without reducing the protective properties of the ting. Once a prototype has been accepted trials would be undertaken in a eleration chamber in parallel with field trail application. Ernal £4,458 Internal £2,043										
Expenditure for financial year	External Total	£21,572 £26,030	(1	xpendit FI) fina		-		Exter Inter	-		26,220 28,26 3	
Project Cost (Collaborative + external + SPEN)	£60	0,000		rojecte or SPEN)9 co	sts	Inter Exter Tota	rnal	f	34,000 33,500 3 9,50 0	
Technological area and / or issue addressed by project	alkyd paint s	ending changes in EEC legislation (anticipated date 2010) will prohibit the two coat kyd paint system used in current practise consequently there is a need to use a safe ternative system.										
Type(s) of	Increm	Incremental Significant Technological Radical						cal				
innovation involved	Yes	5		No				Yes			No)
Expected Benefits of Project	The main bus Reduced exp Reduced exp Application of Outage durat More towers	osure to fall osure to fall osts are ant tion times a	s during s as pai icipated re expe	g tower nters a d to be cted to	acces nd ins 25% fo be red	ss/eg pector or the duce	ress ors sper e same d by 339	nd less degree	time	worki	ng at h	
Expected Timescale to adoption	Αŗ	oril 2009			tion o achie	ved				Jnlimi		
Probability of Success		50%		1	2	3	evelopr 4	nent (Start -	7	ent) 8	9
Project NPV Project Progress March 09	EATL tesStage on	 Stage one is now complete with a trial tower on the ZV route being painted Currently awaiting test report regarding effects on painters during trial tower 										
Potential for achieving expected benefits	On track for	On track for completion of 2^{nd} trial which will be the complete painting of route to be to finish August 2009						o be to				
Collaborative Partners	N/A	N/A										
R&D Providers	Chemco Inte	Chemco International										

Project Title	IFI 0704 - 4energy Low Carbon Comms Cooling
Description of project	Telecom rooms in major grid points on the transmission network contain sensitive electronic equipment e.g. Cisco routers. Recent installations have shown this equipment to be sensitive to temperatures above 40°C.
	This project will develop, test and install innovative low carbon solutions to cool



	telecom equipment and airflows, filter-less cent RFI cabinets will form first such energy saving avoid over 50% of the c	rifugal the te g initia	I fans and t chnical inn tive using t	he imp ovatio hese t	roven n requ	nent d uired.	of mass This is	flow i unde	rates th rstood	rough the to be the
	Internal £4,507		Expenditu	re in		Int	ernal		£3,56	57
Expenditure for financial year	External £17,43	6	previous (ancial	Ext	ernal		£52,4	106
interior year	Total £21,94	2	years			Tot	tal		£55,9	73
Project Cost						Int	ernal		£4,00	00
(Collaborative +	Collaborative + £62,500		Projected 08/09 costs for SPEN			Ext	External			000
external + SPEN)			10. 0. 2.			Tot	tal		£25,0	000
Technological area and / or issue addressed by project	Currently 10 out of 19 sites utilise traditional air-conditioning. It is proposed to trial 4energy's cabinet cooling solution in all our 19 existing sites. The whole room cooling solution is to be trialled on 3 sites, if successful could be deployed into all 130-transmission substations.									
Type(s) of	Incremental		Significant Technological substitution						F	adical
innovation involved	Yes		No			1	No			No
Expected Benefits of Project	The implications of this Telecommunication installed. The installation of the cooling solution footprint of almost	ns with expens n with	n grid sites sive buildin ~2MW of p tonnes of C	may bo g servi bower CO ² per	e comp ces air each y	conc	litionin	g is be	ing spe	cified as
Expected Timescale to adoption	1 Year		Duration benefit achieve	once				10 Y	ears	
Probability of									urrent)	
Success	50%		1	2	3	4	5	6	7	8 9
Project NPV	(Present Benefits x Prob Present Costs	pability	y of Success	5) –		ba	sed on	£905 comm	ns room	n cooling
Project Progress March 09	Cooling alternatives to Without the RFI Cool s telecoms rooms in ord reduction from 'RFI cool 35°C without any harm use the Directed Air temperatures will rem conditions. Following the installation the telecom rooms has environmental temperatures than 40°C.	system der to ol' mea oful eff solution ain ur on of ave be	the use of keep Ciscons that the fects on the on developed and the Directed the Directed and the Directed the	fair concept of the c	onditioning on the control of the co	oning below eratur . This this I o cabi ns wir	in sur 40°C re can l opens FI pro inets u	Howe be safe up the ject wander ander	ever, tely elevate opposition generated the second	he 8-10°C ated up to ortunity to guarantees w climatic ' filtration on outside



	The proposal is to install energy efficiency cooling in telecommunication rooms in major grid sites in which Cisco servers are being located. This initiative will deliver a saving of 20% on the capital cost of installing traditional vapour compression air conditioning.
Potential for achieving expected benefits	Once installed a greater than 90% saving versus estimated air conditioning power savings will be made in those telecommunication rooms.
	Strategic telecoms are looking to install units in a further 10 sites in SPT before the end of 2008.
Collaborative Partners	N/A
R&D Providers	4Energy

R&D Providers	4Energy								
Project Title	IFI 0706 - Ashton Hayes	Microgrid	1						
Description of project	Ashton Hayes, a village r (http://www.goingcarbo carbon saving initiative buildings are close toge hall and school have ex and dCHP).	nneutral.c s includin ther; nam	co.uk/). The g small-scale nely the chur	village is generati ch, Wome	pursuing a on. A nur n's Institut	number of different mber of community e's (WI) hall, village			
	Internal £5,146	5	Expenditu	re in Int	ernal	£2,819			
Expenditure for financial year	External £44,87	74	previous (I	FI) Ex	ternal	£1,758			
····airoiai yeai	Total £50,03	19	financial y	ears To	tal	£4,577			
Project Cost			Projected	Int	ernal	£0			
(Collaborative +	£56,500		09/10 cost	s for Ex	ternal	£0			
external + SPEN)		SPEN		tal	£0				
and / or issue addressed by project	It is envisaged that this will develop a simple strategy that can be used by the SP Energy Networks' Connections business to determine at which points different network technologies should be introduced to facilitate the connection of generation. Although developed using this network as a case study, the project will look to develop common, simple solutions. Technological Radical								
Type(s) of innovation involved	No		No		es	No			
Expected Benefits of Project	No No Yes No The impact on adjacent parts of the network and the implications of legacy equipment will be taken into account. In the case of Ashton Hayes the most appropriate technology will be identified, which allows more generation to be connected but that is flexible to future changes to the network but also is as simple as possible. The work will aim to be relatively high level and be as generic as possible to enable its conclusions to act as a guide for other								
Expected Timescale to adoption	1 Year		Ouration of bonce achieved			20 Years			
		· · · · · · · · · · · · · · · · · · ·	·	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·				



5 1 1 1111 6		TRL Development (Start – Current)									
Probability of Success	50%	1	2	3	4	5	6	7	8	9	
Success											
Project NPV	(Present Benefits x Probability of Costs	(Present Benefits x Probability of Success) – Present Costs £7,549									
Project Progress March 09	A report was produced by EATL that surveys literature and projects regarding small-scale generation. It then outlines the network issues and the relevant standards and policies for the LV network. Potential solutions and the additional benefits are identified. Models of a rural and urban network are used to establish the level of generation that will cause problems for the LV network and the frequency and severity of the problems. Conclusions and recommendations have been drawn from the work.										
Potential for achieving expected benefits	The recommendations should indicate the actions ScottishPower may need to take to accommodate increasing levels of connection of generation to the LV network and the potential to develop a more active LV network.										
Collaborative Partners	Ashton Hayes village										
R&D Providers	EA Technology										

Project Title	IFI 0707 - Wi	nd Turbine	Effects on	Transmissi	on Line	s			
Description of project	The scope of the project is to determine the magnitude of the problem from constant speed and or variable speed wind generators through research / investigation on the effects of the wind pattern (down wind of wind turbines) on the structure and spans of adjacent overhead line. Modern wind turbines can be as large as 80m diameter (for 1MW+). Behind the turbine, the mean wind speed/pressure can be reduced, and turbulence severely increased. The reduced pressure of the new wind pattern created by the rotating blades is considered likely to affect a structure / overhead line in the vicinity of wind turbines.								
Evpanditura for	Internal	£17,5	533	Expenditure in		Internal	£1,928		
Expenditure for financial year	External	£22,6	515	previous	. ,	External	£6,158		
·	Total	£40,1	148	financial	years	Total	£8,086		
Project Cost			Projected 08/09 costs for		Internal	£7,000			
(Collaborative +	£70,000				External	£55,000			
external + SPEN)				SPEN		Total	£62,000		
Technological area and / or issue addressed by project	site, which c developmen transmission	onsequent ts are now connecte here is a	ly required being pursu d windfarm need to ur	33kV connued that red	ection. quire tra evelope	Posts SRO a n ansmission con ed and the st	pment at 15MW per umber of large scale inections. With more andard turbine size on adjacent tower		
Type(s) of	Increme	ental	Signif	icant		hnological bstitution	Radical		
innovation involved	Yes		N	0		No	No		
Expected Benefits of Project	Through a better understanding of turbine wake effects mitigating measures can be factored into windfarm connection design in order to maintain the integrity of the local transmission supply, therefore avoiding unforeseen outages and decreased network reliability.								



Expected Timescale to adoption	3 Years	Duration of benefit once achieved						20 ye	ars	
Probability of				TRL De	velopm	ent (S	tart – (Current)	
Success	50%	1	2	3	4	5	6	7	8	9
	/D	t f C.		Duna				<u> </u>		
Project NPV	(Present Benefits x Probabili Costs	ty of Si	uccess)	– Pres	ent			£835,4	66	
Project Progress March 09	The report covers Stage 2 of nearby overhead lines. A proinvestigate this phenomenor existing ZS OHL Smeaton to 1 is planned to have several 3 report investigated the wake guidance world-wide. This le a wind tunnel to investigate wind turbine over a range of tests were carried out at M test facility. The scale of the Vesta V90-3.0MW turbine. turbulent flow to simulate distances from the turbine a techniques using fog and hel the aero-elastic response a reproducing the dynamic chawas measured in 5 points alothe results of all the above m 1) Anemometric measureme 2) Flow visualizations 3) OHL aero-elastic response	ogrammer and s Forness MW to effect d to the was wind s ilan Poe e wind Experious 1:50 aracter ong the nention	me of very pecificate section of the product of the	vork hally to lad line and position and mand mand mand were also of a sor a 400 sing infivities in	as beer look at the Crysta oned at through of a prowind spoot of the Carried C	n agree one pal Rig verse 135m peed riggram peed riggram in the dout nent. It is were alloyed. The same recommend out the peed of the peed	ed with roject a vhich un from erature me for eduction a rid stare tests using Flow percarried. Tests of the interest of the i	n Scotti associa ises L12 this lin e surve Stage 2 on pher nd orie ndard v is 1:50, both s batterns d out. V were per ductor motion report	sh Pow ted with tower e. An y and e which nomenantation vind tu based smooth at va Visualise (Arauc of the	ver to the the treatment of the the treatment of the trea
Potential for achieving expected benefits	The wind tunnel data sugge conductors at 2.5D from the contacts indicated that the Sweden, the USA and Canada Field tests be carried out These tests be carried out Tests also be carried out These tests to be carried turbine close to and upw Future work should be DNO's through the EA Te In the meantime no win line.	turbindere weed a. It is at subject at subject on all on the ed out vind of carried echnologies.	e. Cont re con therefor o-span of Il phase e earth if poss the line I out ir	act with accerns or ereconduction of the conduction of the conduct	h relevin oth ommen of using a sefore a ceration amme.	ant ex er coo ded th g Sefag tandar and af with	perts wuntries nat: I low from Sefageter ins	vorld-w includ equenc g vibrat tallatio al Grid	ide via ing Au y moni ion mo n of a and th	Cigré ustria, itors onitor wind ne UK
Collaborative Partners	N/A									
R&D Providers	Milan Polytechnic and Hydro	Quebe	ec							

Project Title	IFI 0708 - Health Indices for Asset Management Decision Making
Project Title	iri 0/08 - Health indices for Asset ivianagement Decision iviaking



	EA Technology has of link engineering know	-					_	-		ess to	
Description of project	health index is 'calibi applied that enables individual asset is the asset group and the following four essent • Network Perform • Criticality is expressignificance of a • The impact on as	BRM defines the current condition of individual assets by a numeric 'health index'. This ealth index is 'calibrated' against the probability of failure (POF). An ageing algorithm is pplied that enables the future condition and POF to be estimated. The risk for an idividual asset is the product of the POF, the average consequence of failure for the seet group and the criticality of the asset. Consequences of failure relate to the ollowing four essential categories, which are related to the common unit of money: Network Performance (CMI & CI), Safety, Financial and Environmental Criticality is expressed as a multiplication factor and is the importance or significance of an individual asset relative to other assets in the group. The impact on asset health and subsequent risk can be determined for different investment intervention strategies.									
	Internal £ 1	L3,069		Expendi	ture in	Inter	nal	£ 1	,609		
Expenditure for financial year	External £ 4	15,374		previou	s (IFI)	Exter	nal	£ 1	,758		
,	Total £ 5	58,442		financia	I years	Total		£ 3	,367		
Total Project Costs				Projecte	ed	Inter	nal	£ 0			
(Collaborative +	orative + £ 50,000 09/10 costs for			09/10 c		Exter	External £ 0				
external + SPEN)			Total		£ 0						
Technological area and / or issue addressed by project	(asset criticality). EA Technology's work has been adopted by other DNOs consequently, there is a business requirement to at least understand the effectiveness of this technique either with a view of adopting in support of elements for DPCR5 submissions.										
_	-		ect Ber		Proje	ect Resi Risk	dual		all Proje Score	ect	
Type(s) of innovation involved	Incremental Significant		Rating 12	3		-2	14				
Expected Benefits of Project	 presentation at l Ability to define Ability to advance performance and Assess impact of option 	 Ability to advance age assets to help determine possible future condition, performance and risk Assess impact of different investment intervention strategies and 'do nothing' option 									
Expected Timescale to adoption	2 Years		Durat achie	tion of be	enefit on	ce		5 Yea	ars		
				TF	RL Devel	opment	(Start -	- Current	urrent)		
Probability of Success	50%		1	2	3 (4 5	6	7	8	9	
Project NPV	Present Benefits x Pr	obability	of Suc	ccess) – P	resent C	osts		e conside outcome	-	_	
Potential for achieving expected benefits	As part of SPEN's stu health indices and as	_	-	-			_				



Project Progress March 09	The 'CBRM' process, developed by EA Technology in conjunction with electricity companies over the past 8 years, has been applied to two asset groups (11kV ground mounted CBs and 132kV OHLs). A CBRM report has been produced and CBRM spreadsheets defining a health index for individual assets have been produced for both asset groups.
Collaborative Partners	N/A
R&D Provider	EA Technology Limited

	T							
Project Title	IFI 0709 - Sub.net Mo	nitoring						
Description of	various aspects of the auxiliary contacts of	ne power neto from protection and sends for	work. It is ion relay matted r	connects connects	ted to protect switchgear. S	der, which monitors tion VTs and CTs and Sub.net process the cted on the network		
project	roject It is possible to capture an event and distribute the processed data minutes to the parties that can take the appropriate action. Monitors said early indication of 11kV fault location, confirm that overhead line automation schemes are functioning properly and determine if circuit be times are within acceptable limits, in addition to covering the full range phenomenon.							
	Internal £ 7	,189	Expendi	ture in	Internal	£ 72,920		
Expenditure for financial year	External £ 2	5,049			External	£ 1,609		
	Total £ 3	2,238		,	Total	£ 74,529		
Total Project Costs		Projected 08/09 costs for SPEN		Internal	£ 26,000			
(Collaborative + external + SPEN)	£ 130,000			External	£ 27,000			
external · 3· Eiv		31 211		Total	£ 53,000			
Technological area and / or issue addressed by project	_	e as possible	e and dis	sseminat	ing necessary	e. By processing data information to the ient manner.		
Type(s) of innovation involved	Incremental	Project Be Ratin		Proje	ct Residual Risk	Overall Project Score		
illiovation illvolved		13			-1	14		
Expected Benefits of Project	The project aims to offer improvements in system operation, performance and safety: Reductions in CML and consequent penalty savings will be achieved by timely fault location and appropriate restoration Monitoring of protection systems ensure that protection settings are optimised and voltage dip durations are minimised Safety and performance improvements realised by monitoring operating times of circuit breakers and substation battery supplies Down stream fault clearance times and circuit breaker operating times would be sent direct to protection and maintenance engineers respectively in thus reduce CML and CI by prevention Web Access negates the requirement for a base station to dial in/out and offers roving accessibility. No polling and central processing requirements							



Expected Timescale to adoption	1 Year	Duration of benefit once achieved 20 Years								
				TRL De	velopn	nent (S	Start – C	Current)	
Probability of Success	70%	1	2	3	4	5	6	7	8	9
									>	
Project NPV	(Present Benefits x Probability	Present Benefits x Probability of Success) – Present Costs No NPV calculated for this limited trial								or this
Potential for achieving expected benefits	Currently developing in-house automatic impedance mapping to identify fault location quicker									
Project Progress March 2008	 All units have now bees sub.net unit to calculate Trip oil timing – If trip of automatic emails are ser There have been some is on the way to being reso We have been able to if found slow or 'sticky' brees 	distander close of to make to make well with the make well with the make th	time i time i aintena vith firr	ault instance to mware fance to inware	talled vith lim highlig and co ults an	nits for ght pos mmun d rem	particussible polication	ular cir roblem s but th	cuit brons. nese ar	eaker, e well
Collaborative Partners	None									
R&D Provider	Embedded Monitoring Systems (eMS).									

Project Title	IFI 0710 - GB SQSS Re	eview Studies								
Description of project	the Main Interconne GB Security and Qual make provision for th The aim of Phase 1 proposed planning m to consider the impli	the three GB transmission licensees have been involved in research work to look at how the Main Interconnected Transmission System (MITS) planning rules in Section 4 of the B Security and Quality of Supply Standards (GB SQSS) should be adapted or changed to make provision for the increasing volume of wind generation connected to the network. The aim of Phase 1 of this project is to carry out further studies to ensure that the roposed planning method is robust. Also, further work in Phase 2 is to be carried out to consider the implications of the rule on generation market access and facilitation of competition in this market.								
	Internal £ 3,502				Internal	£ 1,609				
Expenditure for financial year	External £ 1	0,707	Expenditure in previous (IFI)		External	£ 9,482				
a yea.	Total £ 1	4,208	financia	l years	Total	£ 11,091				
Total Project Costs			Projected		Internal	£ 4,000				
(Collaborative +	£ 60,000	09/10 costs for		External	£ 18,000					
external + SPEN)			SPEN		Total	£ 22,000				
Technological area and / or issue addressed by project	could have a conside	At this stage it is very important to test the proposed planning rule thoroughly, as it could have a considerable impact on the level of transmission capital expenditure by the transmission licensees if it is adopted for the GB SQSS.								
Type(s) of innovation involved	Incremental / Significant	Project Be Ratin		Proje	ct Residual Risk	Overall Project Score				
minovation involved	Jigiiiiicaiit	11			-7	18				



Expected Benefits of Project	 The project will develop a common, well tested, set of rules based on a number of generation/demand scenarios that will be adopted by the collaboration partners to ensure a consistent approach between the three transmission licence areas. The new MITS planning rules will help to defend investment decisions in future Transmission Price Control Reviews The role and impact of wind generation on the transmission network will be better understood, with all generation treated on an equal basis. 										
Expected Timescale to adoption	2 Years Duration of benefit once achieved 10 Years										
				TRL De	velopn	nent (S	tart – C	Current	rent)		
Probability of Success	60%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Probability	of Suc	cess) –	Prese	nt Cost	S		uantify	s unabl , analys omes.		
Potential for achieving expected benefits	Despite the project being in fundamental review of the continues, using the results a	SQSS.	A nev	v MITS	worki						
Project Progress March 2009	The new MITS working group is now developing cost-benefit models that consider transmission investment cost (T), operational costs (O) and the cost of unprovided energy (X) over a number of years (T+O+X model). This model will provide information, not only on the treatment of wind, but also on other SQSS aspects such as the use of appropriate contingencies in planning studies. The development of the TOX model is in an advanced stage and testing continues.										
Collaborative Partners	National Grid Electricity Transmission plc and Scottish Hydro Electric Transmission Limited.										
R&D Provider	TNEI Services Ltd, Strathclyde	Unive	rsity, lı	mperia	l Colleg	ge (SED	G)				

Project Title	IFI 0711 - 3 rd Party ROEP Risk Assessment							
Description of project	a new concept of achieved under Power, and was classification of (ROEP). The theo which includes development at In this project, it of the developes sites). This will addition, a use assessment of	It of the so-called " f safety limit curve National Grid rese completed in Autu substations into l pretical studies to c the use of histo Cardiff University. Is proposed to cord 'Stage I' technique allow a refined qual er-friendly procedusites. The ultimatengineers making	s, where standard arch project NSET umn 2006. The State ow/high risk cated evelop a Stage II prical operational aduct pilot studies, ue at identified keantification of risk ure will be devete purpose of the	fault clearance tin S180 in collaborating of the second of	nes are used, was zion with Scottish and enables broad f Earth Potential drisk assessment, are now under limplementation abstations (4 to 5 a ALARP levels. In easy and quick or provide better			
Francisco di transfera	Internal	£ 4,074	Expenditure in	Internal	£ 1,609			
Expenditure for financial year	External	£ 4,458	previous (IFI) financial years	External	£ 26,058			
	Total	£ 8,532	,	Total	£ 27,667			



Total Project Costs (Collaborative +	£62,000 (Nation	al Grid	Projected [ne		Internal	£ 2,000		
external +	contribution £3		year] compai		External	£ 29,000		
[company])					Total	£ 31,000		
Technological area and / or issue addressed by project	_					determine whether or danger of third party		
Type(s) of innovation involved	e.g. Incremental Tech Transfer Significant	Project Be Ratir	ct Residual Risk	Overall Project Score				
imovación involved	Radical	7			-3	10		
Expected Benefits of Project	There are many sites in Scotland and Manweb where the existing sites do not have earthing that has been installed to the current standard. System fault levels have been increasing due to the significant amounts of renewable generation that has been connected (with bigger schemes in the construction and planning stages). If current system fault levels are applied to these sites there is a potential that the touch/step voltage levels will be too high to allow work to commence without further costly mitigation measure being implemented. This tool would allow an assessment to be made of what the probability would be of a life-threatening fault appearing at the substation so that the appropriate corrective action can be taken. The user friendly interface package will allow SPEN staff to carry out assessments of earthing systems using statistical fault levels and clearance times values as opposed to worst case. By being better equipped to assess the potential risk posed by existing substation earthing arrangements appropriate steps can be taken, which could be the avoidance of unnecessary expenditure on inappropriate mitigation measures. The software analysis will help to justify Third party mitigation measures.							
Expected Timescale to adoption	1 Year	Du	ration of achi		nce	4 Years		
Probability of Success	75%		ject NPV = / Costs) x Suc	-		£ 15,562		
Potential for achieving expected benefits	Potential – The project is progressing to a next stage where the following items will incorporated into the software: • Set up of fault clearance time database • Calculate variation in fault current magnitude and its effect on prediction of individual risk • Apply extended computer procedure to several case							
Project Progress March 09	First stage of this project is completed and demonstrator software was developed for determining hot zones within substations taking into account parameters such as grid size, mesh density, earth resistivity and body resistance.							
Collaborative Partners	National Grid							
R&D Provider	Cardiff University Hig Griffith).	Cardiff University High Voltage Energy Systems research group (Manu Haddad & Huw Griffith).						



Project Title	IFI 0712 - BT 21 st Cent	tury Protectio	n Solutio	ns (BT210	CN)				
Description of project	The change of BT's network to an IP based system (BT21CN) is posing some significant risks to the performance reliability of the SP-M and SP-D electricity networks. In particular SP-M relies heavily on 3 rd Party leased services from BT as the communications for the 33kV network protection in rural areas. The strategy to mitigate the problem has been developed based on the utilisation of a range of communications solutions (fibre, radio, power line carrier in addition to technically/commercially suitable BT services) in a coordinated manner. Whilst this strategy has been agreed in principle, there are several technical challenges associated with several of the solutions. This project aims to provide the detailed and engineered communications channels that underpin the toolbox of solutions to mitigate the problems associated with BT21CN.								
Expenditure for		0,531	Expendi		Internal	£ 1,609			
financial year		9,031	previous financia		External	£ 1,758			
	Total £ 9	9,562			Total	£ 3,367			
Total Project Costs			Projecte		Internal	£ 15,000			
(Collaborative + external + SPEN)	£114,000	1	08/09 co	osts for	External	£ 43,000			
,					Total	£ 58,000			
Technological area and / or issue addressed by project	 includes: Power Line Carrier deployment at 33kV combining protection and SCADA signalling Small development works to facilitate intra-substation communications IP based protection signalling mediums and associated security implications Options for alternative communication channels for shared services Implications for the network in no cost effective solutions are realised Project Benefits Project Residual Overall Project 								
Type(s) of innovation involved	Significant / Project Be Rating Technology Transfer		-		Risk	Overall Project Score			
		21		2		19			
Expected Benefits of Project	There are many sites in SP-M where there is no Line-of-Site for radio communications and fibre installations are extremely expensive due to excessive circuit lengths. In such sites Power Line Carrier (PLC) or Leased services are the only feasible communication medium for protection signalling. PLC is typically deployed at higher voltage levels, additionally some development work facilitated in a trial would be required to accommodate protection and SCADA data on the same link however this could deliver a more cost effective alternative to fibre or BT SDH leased services. Power Line Carrier although a viable solution has some limitations, which restrict its use on the network, mainly mid-circuit transitions (OHL – Cable), which cause the signals to reflect. Where PLC cannot be deployed alternative will require consideration. Leased services (or no communications at all) are the only alternatives to expensive infrastructure at some sites. SDH services can be expensive in terms or both CAPEX and OPEX. BT are likely to offer IP based products in the future (products not currently used with protection). If development is carried out to facilitate the use of IP based products for signalling purposes factoring in security considerations then it may be possible to leases services at significantly reduced CAPEX and OPEX costs.								
Expected Timescale to adoption	1.5 Year		Duratio achieve	n of bene d	fit once	15 Years			



		TRL Development (Start – Current)								
Probability of Success	50%	1	2	3	4	5	6	7	8	9
								\geq		
Project NPV	(Present Benefits x Probability of Suc	cess) -	- Pres	ent Co	sts			£951,	763	
Potential for achieving expected benefits	currently considered for use with p communications are the only of	In areas of the network where protection signalling cannot be delivered via channels currently considered for use with protection devices without significant expense, leased communications are the only option. Should a suitable leased or alternative communication bearer be unavailable then significant investments in fibre optic installation will be required.								
Project Progress March 2008	 Inter-substation communications equipment between legacy protection equipment and new equipment achieved with the aid of sub-rate MUX used developed to SP requirements. The trialling of radio technology for use on non L-O-S links (marginal links) with protection devices is underway. If trial successful an alternative potentially cheaper communication for use with protection with CAT 1 signalling channel requirements may be available for deployment of a number of sites where communications provision is difficult/expensive Works carried out on an IP network test-bed to assess the feasibility of running TDMoIP protection signalling, work underway to trial this solution in a substation environment. 									
Collaborative Partners	N/A									
R&D Provider	RFL / C & W / Radius / Tait / others TBC									

Project Title	IFI 0801 - IEC	61850 Application in	SP - Transmission						
Description of project	The key objective of this project is to maximise economic and effective utilisation of the transmission asset and network. The deployment of the technology advocated for this IFI project will allow ongoing substation secondary equipment retrofitting (refurbishment) projects to proceed whilst limiting the duration and frequency of circuit outages, required to facilitate the work.								
Expenditure for financial year	Expenditure in Expenditure in previous (IFI) financial years			Internal External Total	£0 £0 £0				
Total Project Costs (Collaborative + external + SPEN)	£455,000		Projected 09/10 costs for SPEN	Internal External Total	£15,000 £80,000 £95,000				
Technological area and / or issue addressed by project	Project 1 (IFI 0801-1) – Microsol This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely: a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay. At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring. Project 2 (IFI 0801-2) - University of Manchester and NGC This IFI application aims to investigate, quantify and optimise the level of security,								



	l :	dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.									
	GE Multilin are first undertake a field tria testing of the scheme Proof that the prote conventional schemes To gain experience of system.	o gain experience of the installation, configuration and operation of a process bus									
Type(s) of innovation involved	Significant	Benefit ing	S	Pro	ject Res Risk	sidual		Overa So	ll Proje core	ect	
		1	7			-7				24	
Expected Benefits of Project	In summary, if this posuccessfully on our M will fundamentally in manufacturer, and w expensive option of environment and ado However, IEC61850 a services has been deprovide significant p installation and testin Additionally, part 9-2 wiring, provide additireplacement.	licrosol RTU fluence dec ill have the flood wiring pting a LAN also offers monstrated erformance g times as r permits the	then in the second seco	t gives regard advamultiach to ts in the Wefits ouf the sfapro	s us s ding s antag core comi the p st Co yer h schem	ome re substati e of all copper ms and rotection ast open ard-wir ne functions whi	al flex on decowing cable data con pon rea eration ing ar tionali	ibility sign a gus to es with capture alm. T hal Int hd sig ty can h, in a	for the nd chool cease in the e. the use tertrip nificant be facuation	of G sthe I subst of G schem tly rec tory to	e and relay nighly cation OOSE ne) to duced ested. duced
Expected Timescale to adoption	1 Year			ration once a					10 Yea	rs	
				T	RL De	velopm	ent (S	tart –	Curren	t)	
Probability of Success	75%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pro	bability of S	uccess) – Pre	esent	Costs	_		£1,72	9,410	
Potential for achieving expected benefits	This project is on track	k with Proje	ct 1 to	be co	mplet	ted late	2009				
Project Progress 09	We have now successfully recovered data using MODBUS over TCP/IP from the fault recorder and are in the process of putting this online at Busby 275kV before moving on to the IEC61850 part of the development. Several meetings with Microsol to discuss technical issues and also a kick off meeting to scope out project requirements with Microsol and Qualitrol										
Collaborative Partners	Project 1 and 3 none,										
R&D Provider	Manchester Universit	у									



Project Title	Strategic Technology Programme: Overhead Network Module 2						
Description of project	A DNO research & de	velopme	nt collaboratio	on hosted by EA	Techno	ology	
Expenditure for financial year	Internal £ 6,952 External £ 43,802 Total £ 50,754		Expenditure (IFI) financia	•	Intern Extern Total	•	
Project Cost (Collaborative + external + SPEN)	£310,102 + DN	0	Projected 09	9/10 costs	Intern Extern Total		
Technological area and / or issue addressed by project	performance of over negative impact on co positive impact on sa problems that have significant and which	The Module 2 programme for budget year 2008/9 aimed to reduce costs and improve performance of overhead networks by increasing understanding of issues that have a negative impact on costs and performance. The programme is expected to also have a positive impact on safety and environmental performance. The projects all address real problems that have been identified by the module steering group members as significant and which require technical investigation and development. Updated information can be found at:- https://www.stp.uk.net					
Type(s) of innovation	Incremental, Tech Transfer,	_	Project Benefits Project Resid Rating Risk			Overall Project Score	
involved	Significant, Radical		15	-9		24	
Expected Benefits of Project	 Projects in this module will significantly increase the safety and reliability of the network. In certain cases the asset life may also be extended. If these projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO member of the programme to gain benefits including: Cost effective and early identification of damaged insulators and discharging components, which if not addressed would result in faults; Reduce levels of premature failure of assets and so avoid of risk of injury or loss of life or damage to property as a result of falling overhead lines; Avoid redesign, reconstruction or refurbishment of overhead lines where this is driven by a perceived need to increase ratings or strengthen lines, and is required to conform with existing standards but which may be unnecessary; Co-operation between European countries in the development of forecasting methods of atmospheric icing and for the exchange of forecasting tools; Comparison of new covered conductor with known performance of older types Extend the service life of towers and reduce potential levels of tower failures; Review alternatives to wood poles; Reduce lifetime costs by the appropriate use of alternative materials; Give Members a better understanding of novel conductors for new-build or reconductoring 132kV wood pole lines that gives lower capital cost, minimum visual impact, environmental acceptance than other methods of improving power transfer. 						
Timescale to adoption	Range 2-5 years dep on project	endent		f benefit once lieved		lange 2-10 years pendent on project	
Probability of Success	Range 10-50% - depo on project	endent	– PV Costs)	= (PV Benefits x Probability uccess		£64,624	
Potential for achieving expected benefits	A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Projects Still In Progress (March 09):- S2110_4 Extend OHRAT to include User Defined Covered Conductor S2136_4 & 4A European Project COST 727: Measuring and forecasting atmospheric						



	ising on structures, including Crash iso motor trial.
	icing on structures, including Czech ice meter trial; S2143_3 Develop in-situ degradation monitor for Al OHL conductors - Stage 3
	Instrument Development;
	S2147_2 Increasing vibration limit of CCs to 20%UTS using multiple std or single Hi-mass
	SVDs
	S2151_2 Alternatives to wood poles - Stage 2: Erection and fitting trials on concrete
	poles
	S2154_2 Experimental investigation of novel conductors at Deadwater Fell – Stage 2:
	Vibration;
	S2157_1 Novel conductors for 132kV wood pole lines;
	Most projects or project stages started in the module during 08/09 have been
	completed, but some projects span more than one year.
	Completed Projects (March 09):-
	S2126_4 Monitoring conductor temperature at fixed current – at Cashlie and
	Queensferry;
	S2132_2 Validation of ice accretion models using Deadwater Fell;
	S2136_3 Continued involvement with European Project COST 727;
	S2138_2 Investigation of live-line jumper-cutting limitations;
	S2143_2 Develop in-situ degradation monitor for aluminium OHL conductors – Stage 2:
Project Progress to	Feasibility study;
March 09	S2146_2 Torsion tests on composite insulators - Stage 2: Effect of torsion on tension
Widi cii 05	insulators;
	S2149_2 High durability OHL fittings - Stage 2: Costing for testing prototype high
	durability fitting;
	S2150_1 Evaluation of TDR for assessment of tower foundations;
	S2152_1 Evaluate performance of Czech Icemeter at Deadwater Fell;
	S2153_1 Suitability of hand-held PD detector for condition assessment of pole-top
	equipment;
	S2154_1 Experimental investigation of novel conductors – Stage 1: Icing;
	S2156_1 Build Three Prototype Field Pole Leakage Current Detectors;
	S2159_1 LV shrouding - review of current practices and standards
Collaborative	All DNOs
Partners	All DIVOS
R&D Providers	EA Technology

Project Title	Strategic Technology Program	Strategic Technology Programme: Cables Module 3							
Description of project	A DNO research & development collaboration hosted by EA Technology								
Expenditure for financial year	Internal £ 6,952 External £ 53,681 Total £ 60,733	Expenditure in previous (IFI) financial years	Internal £19,562 External £175,666 Total £195,228						
Project Cost (Collaborative + external + [DNO])	£375,767 + DNO	Projected 09/10 costs: £387,037	Internal £6,000 External £55,291 Total £61,291						
Technological area and / or issue addressed by project	developing opportunities to r of whole life cost through gr associated accessories comes 3 worked with other Modules Completed Projects (March O S3132_12 & 15: CRATER Near S3148_4 Requirements for of feasibility of earthing and bor	reduce the costs of owning eater reliability and improvement of Module to achieve common goals. 19):- Real time Determination & earthing and bonding of single core MV cable controlling thermo-mechan	ingle core MV power cables: e systems; nical forces in cables systems:						



Comparative field trials; \$3151_2 & 3 Understanding and controlling thermo-mechanical forces in cables systems: Modelling of thermo-mechanical forces in cable systems: Modelling of thermo-mechanical forces in cable systems: Modelling of thermo-mechanical forces in cable systems: S3155_1 Partial discharge testing of MV cable systems to provide asset risk management data; \$3164_1: Develop fluid filled cable design tool; \$3165_1: Performance ageing tests on polymeric terminations \$3166_1 & 2: Performance of cold- and heat-applied accessories under resin: Assessing interaction between resin and semi-conducting layer; Updated information can be found at:- https://www.stp.uk.net Project Benefits Type(s) of Incremental, Tech Transfer, Significant, Radical If the projects are technically successful and the findings and recommendations from the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: • offset future increases in CAPEX and OPEX; • CI/CML savings per connected customer; • Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; • CI/CML savings per connected customer; • Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; • Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; • Reduce design costs. • Increased safety of staff and public by reducing the number of accidents / incidents. Expected Timescale to and project Range 1-3 years - dependent on project Probability of Success A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it'								
S3144_2: Comparison of processes for the treatment of redundant fluid filled cables: Comparative field trials; S3151_2 & 3 Understanding and controlling thermo-mechanical forces in cable systems: Modelling of thermo-mechanical forces in cable systems; S3155_1 Trial testing of triplexed cable in plastic ducts; S3157_1 Partial discharge testing of MV cable systems to provide asset risk management data; S3164_1: Develop fluid filled cable design tool; S3165_1: Performance ageing tests on polymeric terminations S3166_1 & 2: Performance ageing tests on polymeric terminations S3166_1 & 2: Performance ageing tests on polymeric terminations S3166_1 & 2: Performance ageing tests on polymeric terminations S3166_1 & 2: Performance of cold- and heat-applied accessories under resin: Assessing interaction between resin and semi-conducting layer; Updated information can be found at: https://www.stp.uk.net		S3153_1 & 2: Economics and development including CO ₂ k S3168_1 & 2: Comparing for current specifications and coresin and semi-conducting la S3169_1: Further studies on S3171_1: Jointing on to wet	d environmental impurden calculation uture designs of H designs and study ayers; the retraction of incables.	ipacts of dist ; V and EHV μ to determin	ribution polymerine the in	cable losses: Model c cables: Review of nteraction between		
S3166_1 & 2: Performance of cold- and heat-applied accessories under resin: Assessing interaction between resin and semi-conducting layer; Updated information can be found at: https://www.stp.uk.net Project Benefits Project Residual Overall Project Incremental, Tech Rating Risk Score		S3144_2: Comparison of processes for the treatment of redundant fluid filled cables: Comparative field trials; S3151_2 & 3 Understanding and controlling thermo-mechanical forces in cables systems: Modelling of thermo-mechanical forces in cable systems; S3155_1 Trial testing of triplexed cable in plastic ducts; S3157_1 Partial discharge testing of MV cable systems to provide asset risk management data;						
Incremental, Tech Transfer, Significant, Radical If the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: • offset future increases in CAPEX and OPEX; • CI/CML savings per connected customer; • Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; • Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; • Reduce design costs; • Reduce design costs. • Increased safety of staff and public by reducing the number of accidents / incidents. Expected Timescale to adoption Range 1-3 years - dependent on project On project Probability of Success Range 15-50% - dependent on project achieved A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year. Other DNOs		S3166_1 & 2: Performance of interaction between resin ar	of cold- and heat-aged semi-conducting found at:- https://	oplied accesson layer; www.stp.uk.i	ories und net			
If the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: offset future increases in CAPEX and OPEX; CI/CML savings per connected customer; Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; Reduce design costs. Increased safety of staff and public by reducing the number of accidents / incidents. Expected Timescale to adoption Range 1-3 years - dependent on project On project Probability of Success Range 15-50% - dependent on project A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to March 09 Collaborative Partners Other DNOs	innovation	Incremental, Tech	Rating	Risk		Score		
the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: offset future increases in CAPEX and OPEX; Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; Reduce cable purchase costs; Reduce design costs. Increased safety of staff and public by reducing the number of accidents / incidents. Expected Timescale to adoption Range 1-3 years - dependent on project Duration of benefit once achieved Project NPV = (PV Benefits - PV Costs) x Probability of Success Potential for achieving expected benefits A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to March 09 Collaborative Partners The projects are implemented, then following benefits, including: A contraction of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception.	voivea	Radical		-8		21		
Timescale to adoption Probability of Success Potential for achieving expected benefits Project Progress to March 09 Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year. Duration of benefit once achieved Range 2-10 years - dependent on project Project NPV = (PV Benefits - PV Costs) x Probability of Success A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year. Other DNOs	of Project	 offset future increases in CAPEX and OPEX; CI/CML savings per connected customer; Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; Reduce cable purchase costs; Reduce design costs. Increased safety of staff and public by reducing the number of accidents / 						
Potential for achieving expected benefits A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to March 09 Collaborative Partners Con project A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Collaborative Partners Other DNOs	Timescale to		Duration of ber	nefit once				
reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception. Project Progress to March 09 Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year. Collaborative Partners Other DNOs			– PV Costs) x Pr			£87,318		
March 09 completed, but some projects span more than one year. Collaborative Partners Other DNOs	achieving expected	reflect the likely full costs outcome of the early stage is	of implementation s positive. Howeve	. These will	be iden	tified providing the		
Partners Other DNOs		Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year.						
R&D Providers EA Technology		Other DNOs						
	R&D Providers	EA Technology						



NETWORKS					
Project Title	Strategic Technology	Programme: Substatio	ons Module 4		
Description of project	A DNO research & dev	elopment collaboratio	n hosted by EA	Technolo	ogy
Expenditure for financial year	Internal £ 6952 External £ 40014 Total £ 46,966	Expenditu previous (years	IFI) financial	Internal External Total	,
Project Cost (Collaborative + external + [DNO])	£313,784 (08/0	Projected £323,200	09/10 costs:	Internal External Total	•
Technological area and / or issue addressed by project	The aim of the 08/09 Sthemes such as life extonstraints, examinati innovative solutions for distributed generation. The majority of project have enabled skills to Key examples of this witransformers are conning significantly to develop implications, utilisation resulted in the creation. Completed Projects (Nos4164_5: Tap changer S4178_2: Impedance Tay S4181_3: Ongoing Prosulted S4222_2: Alternatives Transformers; S4233_1: 145kV Earth S4235_1: Researching S4237_1: Battery Cabit S4238_1: Module 4 Information S4239_1: Research and S4241_1: Study of Circles S4244_1: Review of mind salure; Projects Still In Progrems S4164_5: Tap changer S4178_2: Impedance Tay S4244_1: Review of mind salure; Projects Still In Progrems S4164_5: Tap changer S4178_2: Impedance Tay S4244_1: X/R Extrapol S4224_1: X/R Extrapol S4224_1: X/R Extrapol S4224_1: X/R Extrapol S4224_1: Aquagen reconstruction of the salure s	tension of aged assets on of new technologie or, the impact on substate on networks and conditions to have not only result be developed betweer were the participation is ected within Europe (Sping better understandin, performance and liften of further supplement of further supplement of the End of Substation Bigramme Of Transform nance Testing: Project to ENATS 35-1 Transform nance Testing: Project to ENATS 35-1 Transform nance Testing of Electrical Cities and the End of Substation Bigramme Of Substation Bigramer of Substa	within legal and s, developing ar ation assets of i dition monitoring dition	d heath a n underst increasing technic knowledgers and Eurn, (S4185 n of which I plant, in of these por 2009/2 has; Mainten g Product Methods; it ions during the for Electric	nd safety tanding of, and g levels of ques. ge transfer, they ropean partners. 5_4), reviewing how n has contributed mproving safety projects have 2010. "A Ground Mounted ance Policies; ts; ; ring equipment Equipment; ctrical Plant &
Type(s) of innovation	Incremental, Tech Transfer, Significant,	Project Benefits Rating	Project Resid	uudl	Score
involved	Radical	14	-9		23



Expected Benefits of Project	If the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: • offset future increases in CAPEX and OPEX; • CI/CML savings per connected customer; • Preventing disruptive failures of oil-filled equipment, tapchangers, earth switches increasing safety and avoid unnecessary scrapping of serviceable components will alleviate environmental impact. • Liaison with European Utilities to share new technology and failure modes; Increased safety of staff and public by reducing the number of accidents / incidents.			
Expected Timescale to adoption	Range 1-5 years - dependent on project	Duration of benefit once achieved	Range 2-8 years - dependent on project	
Probability of Success	Range 10-100% - dependent on project	Project NPV = (PV Benefits – PV Costs) x Probability of Success	£67,777	
Potential for achieving expected benefits	A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since it's' inception.			
Project Progress to March 09	Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year.			
Collaborative Partners	Other DNOs			
R&D Providers	EA Technology			

Project Title	Strategic Technology Programme: Distributed Energy Resources Module 5				
Description of project	A DNO research & development collaboration hosted by EA Technology				
Expenditure for financial year	Internal £ 6952 External £ 53,063 Total £ 60,016	Expenditure in previous (IFI) financial years	Internal External Total	£14,767 £147,566 £162,333	
Project Cost (Collaborative + external + SPEN)	£435,001 + DNO	Projected 09/10 costs	Internal External Total	£7,000 £54,358 £61,358	
Technological area and / or issue addressed by project	During the budget year 08/09, Module 5 has consolidated the work programme by clustering much of the work around a number of key issues of relevance in the planning, design and operation of networks for distributed energy resources; namely, fault level management, network losses, load related investment, circuit ratings, power quality and microgrids. Most of the projects aim to increase network performance and reduce risk whilst having a positive impact on DNOs' environmental performance. Completed Projects (March 09):- S5169_1 Route plan to transform networks from passive to active networks S5161_2 Standard Risk Assessment Approach to DNO protection requirements S5183_1 Communications for active network management S5187_1 Module 5 participation in ENARD Annex II DG System Integration S5188_1 & 2 Latest developments in issues associated with low carbon network designs S5189_1 Techniques for assessing harmonic distortion from generation plant S5193_1 Fault level management S5194_1 Load related investment - Feasibility study S5195_1 Network Losses - Feasibility study S5197_1 & 2 Power Quality Issues - voltage dips and swells S5198_1 Microgrids - Feasibility study				



NETVORKS						
	S5200_1 LV Fuse Reach S5201_1 Distribution Network Losses – Loss Reduction Initiatives					
	Projects Still In Progress (March 09):- S5147_8 Microgenerator clusters - Stage 8 - extension of monitoring / analysis S5151_5 Network Risk Modelling - Stage 5 S5181_1 Effect of low power factor switching S5190_1 Whispergen output characteristic monitoring S5204_1 Monitoring and impact of domestic heat pumps S5205_1 Fault level management - Feasibility Study.					
	Updated information can be found at:- https://www.stp.uk.net					
Type(s) of innovation	Incremental, Tech Transfer, Significant,	Projec	ct Benefits Rating	Project Residua Risk	l Overall Project Score	
involved	Radical		9	-10	19	
Expected Benefits of Project	Projects within this module have been cost effective and help improve reliability and safety of generation connection in distribution networks in line with government policy. If the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO member of the programme to gain benefits including: Contributing to the achievement of Government white paper aims of introduction of significant numbers of micro-CHP units to the UK homes by 2010 and greater numbers beyond then; Paving the way for more actively controlled networks in support of a move to a lower carbon economy; Enhancing the knowledge and awareness of overseas best practice in DG system integration, which can be applied, as appropriate in the UK; Reduction in the cost of connections for developers seeking to connect load and distributed generation; Understanding of the potential to use the Synergy / IMASS connection modelling tool to simplify / reduce the cost of providing indicative connection costs; Developing a more consistent, knowledgeable and auditable application of LV fuse reach across the network, hence a more reliable network reducing CML/CI; Being better placed to assess the possibilities for real reductions in losses on DNO networks to reduce GB GHG emissions; Understanding how to accommodate energy saving technologies such as heat pumps into distribution network design.					
Timescale to adoption	Range 1-7 years - depo on project	endent		of benefit once chieved	Range 1-15 years - dependent on project	
Probability of Success	Range 5-60% - depend project	lent on	Project NPV = (PV Benefits – PV Costs) x Probability of Success		£89,367	
Potential for achieving expected benefits	A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. However, STP has delivered a number of notable innovations since it's' inception.					
Project Progress to March 09	Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year.					
Collaborative Partners	Other DNOs					
R&D Providers	EA Technology					
	•					

